



DRAFT

REMEDIAL INVESTIGATION

REPORT VOLUME VI

**HOOKER/RUCO SITE
HICKSVILLE, NEW YORK**



PREPARED BY:

LEGGETTE, BRASHEARS & GRAHAM, INC.

**APRIL 1990
(REVISED AUGUST 1992)**



APPENDIX 12
Logs of Wells Installed in 1983

HKR 001 1279

WELL LOG

LEGGETTE, BRASHEARS & GRAHAM, INC.
CONSULTING GROUND-WATER GEOLOGISTS

72 DANBURY ROAD
WILTON, CT. 06897

OWNER Whiteman, Osterman & Hanna
Former OCC Ruco Division
Hicksville, New York

WELL NO. Site A

DATE 08/24/83 PAGE 1 OF 3 PAGES

		DEPTH IN FEET		DESCRIPTION
		FROM	TO	
LOCATION	North side of plant east of Tech. Service Lab	Grade	0.5	Brown soil consisting of silt and very fine sand; no odor.
DATE COMPLETED	September 2, 1983	0.5	2.5	Silt, and very fine sand, brown and subangular
DRILLING COMPANY	R. H. Lauman & Associates, Inc.			pebbles. (Split spoon).
DRILLING METHOD	Cable Tool	3	5	Pebbles and cobbles; some gravel, very coarse
SAMPLING METHOD	Split Spoon & Bailer			sand and tan clay. (Bailer sample).
AMPLES EXAMINED BY	J. Naso	5	7	Sand, very fine to coarse, tan to brown,
REFERENCE POINT	R. Lamonica			pebbles, and cobbles. (Split spoon).
ELEVATION OF R.P.	Grade 134.2 ft. above MSL	5	10	Cobbles, pebbles, and very fine to very coarse,
WELL CONSTRUCTION SCREEN TYPE	wire-wrapped stainless steel			tan to brown sand. (Bailer sample).
	2-inch 10	10	12	Sand, very coarse, tan, gravel and pebbles.
SETTING	A-2 105 to 112 ft.; A-1 54 to 67 ft. BGL			(Split spoon).
GRAVEL PACK SIZE	Grade 1 New Jersey*	10	15	Gravel, cobbles and very fine to very coarse,
CASING	2-inch stainless steel			tan to brown sand. (Bailer sample).
DEVELOPMENT	A-1 10 hrs. air-lift	15	17	Sand, very fine to very coarse, tan to brown,
	A-2, 3 hrs.			and gravel. (Split spoon).
UMPING TEST	None	15	20	Gravel, cobbles and very fine to very coarse,
DATE				tan to brown sand. (Bailer sample).
DURATION	A-1 78.46 ft MSL	20	22	Sand, very fine to coarse, tan to brown, and
STATIC WATER LEVEL	A-2 78.15 ft MSL			gravel; some pebbles and silt. (Split
PUMPING WATER LEVEL	A-1 1 gpm			spoon).
YIELD	A-2 7 gpm			
REMARKS:	Portland cement - Deep zone: 100 to 80 feet.	20	25	Gravel, pebbles, cobbles, very fine to very
	Shallow zone: 48 feet to grade.			coarse, tan to brown sand and silt.
	*Gravel pack -			(Bailer sample).
	Deep zone: 115 to 101 feet with addition of very fine sand pack from 101 to 100 feet.	25	27	Sand, very fine to very coarse, tan to brown;
	Shallow zone: 48 to 80 feet.			silt and gravel; some pebbles. (Split spoon).

OWNER

Whiteman, Osterman & Hanna, Former OCC Ruco Division, Hicksville, New Yc

WELL NO.

Site A

PAGE 2 OF 3 PAGES

DEPTH IN FEET FROM TO		DESCRIPTION
25	30	Sand, very fine to very coarse, tan to brown; gravel and pebbles; some cobbles. (Bailer sample).
30	32	Sand, fine to medium, tan; some gravel. (Split spoon).
32	35	Sand, fine to coarse, tan; gravel, and stones; no odor. (Bailer sample).
35	37	Gravel and fine to coarse tan, sand and stones. (Bailer sample).
37	41	Gravel and fine to coarse tan, sand and stones; some iron oxide; no odor. (Bailer sample).
41	43	Gravel and fine to coarse tan, sand and stones; some iron oxide; no odor. (Split spoon).
41	45	Sand, fine to medium, yellowish-tan; some gravel. (Bailer sample).
45	47	Top 6 inches: Sand, fine to medium, red and tan; trace gravel. Middle 6 inches: Sand, fine to medium, tan; trace gravel. Bottom 6 inches: Sand, fine to medium, red; trace white clay. (Split spoon).
45	50	Sand, fine to medium, multicolored with red, yellow and gray sandy clay, clayey sand; few white-gray clay streaks. (Bailer sample).
50	52	Sand, fine to medium, and tan, red, yellow, white, gray, clayey sand and sandy clay. (Split spoon).
50	60	Sand, fine to medium, and tan, red, yellow, white, gray, clayey sand and sandy clay. (Bailer sample).
60	65	Sand, fine, tan and red, layers of multicolored (red, white, gray, yellow) clay, sandy clay and clayey sand; some fine gravel, trace red silt or clay.


HKR 001 1281

DEPTH IN FEET FROM TO		DESCRIPTION
	63	Sand, fine, tan and red, layers of multicolored (red, white, gray, yellow) clay, sandy clay and clayey sand; some fine gravel, trace of red silt, clay and large fragments of conglomeratic oxidized sandstone. (Bailer sample).
65	70	Sand, fine, some medium and coarse; and streaks fine multicolored sandy clay and clayey sand; some streaks clay. (Bailer sample).
70	72	Sand, fine to medium; some yellow silt. (Bailer sample).
72	74	Sand, fine to medium, trace yellow silt.
		Bottom 1 inch: Multicolored clayey sand. (Split spoon).
77	86	Sand, fine to medium, tan; streaks multicolored (red, white, yellow) sandy clay, clayey sand and clay, and iron concreted sandstone. (Bailer sample).
87	89	Sand, fine to medium, tan; streaks white clay, sandy clay and clayey sand. (Bailer sample).
	89	2 to 3-inch layer of clay, light gray with streaks multicolored sandy clay. (Bailer sample).
90	92	Sand, fine, tan, streaks light gray clay; some mica. (Bailer sample).
92	106	Sand, fine, tan; some white, trace red clay, sandy clay and clayey sand. (Bailer sample).
106	109	Sand, fine, some medium, tan; trace white, some red silt and clay. (Bailer sample).
109	112	Sand, fine to medium, tan; trace red clay.
112	116	Sand, fine to medium, tan; trace light gray clay. (Bailer sample).
117	118	Clay, sandy clay and clayey sand, black, gray, white, red, interbedded, and stiff.

118 Bottom of borehole.

WHITEMAN, OSTERMAN & HANNA
FORMER OCC PLANTSITE
HICKSVILLE, NEW YORK

CONSTRUCTION
OF MONITOR WELLS AT SITE A



* ALL CASINGS PULLED
DURING WELL INSTALLATION

LEGGETTE, BRASHEARS & GRAHAM, INC.

HKR 001 1283

GEOPHYSICAL WELL LOG

LEGGETTE, BRASHEARS & GRAHAM
CONSULTING GROUND-WATER GEOLOGISTS
72 DANBURY ROAD
WILTON, CT. 06897

OWNER Whiteman, Osterman & Hanna
LOCATION Former OCC Ruco Division Plantsite
Hicksville, New York
WELL NO. A
DRILLING METHOD Cable Tool
DEPTH DRILLED 118 feet
DEPTH LOGGED 114 feet
DEPTH SCALE 20 feet/inch
LOGGED BY Robert Lamonica


DATE August 29, 1983
DRILLER R. H. Lauman & Associates, Inc.
REFERENCE POINT Land Surface
ELEVATION 134.2 feet above mean sea level.
CASING 8-inch to 60 feet; 6-inch to 118 feet;
HOLE DIAMETER 6-inch (inner casing)
REMARKS Static water level about 58.5 feet
below grade.

G A M M A R A Y

SCALE: 16 counts/second/inch
TIME CONSTANT: 3 seconds
LOGGING RATE: 25 feet/minute

Increasing Radiation →

Geol-
ogist's
Log



WELL LOG

LEGGETTE, BRASHEARS & GRAHAM, INC.
CONSULTING GROUND-WATER GEOLOGISTS

72 DANBURY ROAD
WILTON, CT. 06897

OWNER Whiteman, Osterman & Hanna
Former OCC Ruco Division
Hicksville, New York

WELL NO. Site B

DATE 09/07/83 PAGE 1 OF 4 PAGES

	DEPTH-IN FEET		DESCRIPTION
	FROM	TO	
LOCATION	Front of parking		Topsoil, brown, silt, pebbles no odor.
	lot near road		(Split spoon).
DATE COMPLETED	September 14, 1983		Gravel, very fine to medium (1/8 to 2 inch),
DRILLING COMPANY	R. H. Lauman & Associates, Inc.		round to subangular, multicolored; and very
DRILLING METHOD	Cable Tool		fine to very coarse, subangular to angular
SAMPLING METHOD	Bailer and split spoon		tan sand; some brown silt, trace of broken
SAMPLES EXAMINED BY	J. Naso, R. Lamonic, C. Fricke		bricks and glass fragments.
REFERENCE POINT	Land Surface		Discharge = Muddy brown. (Bailer sample).
	130.5 ft. above MSL		
ELEVATION OF R.P.	B-1 132.65 ft. MSL		Gravel, fine to medium, subangular quartz; sand,
	B-2 132.64 ft. MSL		
WELL CONSTRUCTION SCREEN TYPE	wire-wrapped stainless steel		very fine to very coarse; brown.
			(Split spoon).
DIAM.	2-inch slot no. 10		
	104-86 ft.;		
SETTING	69-49 ft.		Gravel, very fine to medium (1/8 to 1 inch),
GRAVEL PACK SIZE	Grade 1 New Jersey*		round to subangular, white; some multi-
CASING	2-inch stainless steel		colored, and very fine to medium, subangular
DEVELOPMENT	B-1 24 hrs. air-lift		to angular, tan sand; little brown silt.
	B-2 4 hrs. air-lift		Discharge - Buff brown. (Bailer sample).
PUMPING TEST	None		Sand, very fine to very coarse, tan; gravel,
DATE			very fine to very coarse. (Split spoon).
DURATION			
STATIC WATER LEVEL	B-1 77.86 ft MSL		Gravel, fine to medium, round to subangular,
	B-2 77.92 ft MSL		
PUMPING WATER LEVEL			multicolored and very coarse to fine,
	B-1 1.5 gpm		angular, tan sand.
YIELD	B-2 3 gpm		
REMARKS:	Portland cement -		Discharge = Buff brown. (Bailer sample).
	Deep zone: 80-69 feet		
	Shallow zone: 44 feet to grade		Sand, very fine to very coarse tan; silt; gravel,
	*Gravel Pack Setting -		fine to medium; brown. (Split spoon).
	Deep Zone: 104 to 81 feet, additional 1 foot of very fine sand pack		

from 80 feet to 81 feet.
Shallow zone: 70 to 44 feet.

DEPTH IN FEET FROM TO		DESCRIPTION
15	20	Sand, very fine to very coarse, angular, tan, and very fine to medium (1/8 to 1 inch) round to subangular, multicolored gravel. Discharge = Buff brown. (Bailer sample).
20	22	Sand very fine to very coarse, subangular to angular; gravel, fine to medium, rounded; brown. (Split spoon).
20	25	Sand, very fine to very coarse, angular, tan, and very fine to fine (1/8 to 3/4 inch), subangular, multicolored gravel; little iron oxide. (Bailer sample).
25	27	Sand, fine to medium, trace coarse; trace of silt; brown with gray streaks. (Split spoon).
25	30	Sand, very fine to coarse, subangular to angular, tan and very fine to medium, round to subangular, multicolored gravel; little iron oxide. Discharge = Buff brown. (Bailer sample).
30	32	Gravel, medium to fine; sand, very fine to very coarse; trace of silt. (Split spoon).
30	35	Sand, very fine to coarse, subangular to angular, tan and very fine to medium, round to subangular, multicolored gravel; little iron oxide. Discharge = Buff brown. (Bailer sample).
34.5	36.5	Sand, fine to medium; some coarse; gravel, fine; brown; trace of red clay. (Split spoon).
35	40	Gravel, very fine to medium, round to subangular, some angular, multi- colored, and very fine to very coarse, angular to subangular, tan, sand. Discharge = Buff brown. (Bailer sample).

DEPTH IN FEET FROM TO		DESCRIPTION
40	42	Sand, fine to very coarse; gravel, fine to medium; brown; trace of iron oxide staining. (Split spoon).
40	45	Sand, very fine to coarse, subangular tan and very fine to fine (1/8 to 3/4 inch), round to subangular, multicolored gravel; little brown silt.
		Discharge = Buff brown. (Bailer sample).
45	46.5	Sand, fine to coarse, brown; trace of gravel; much iron oxide staining at 46.3 feet. (Split spoon).
46.5	47	Sand, fine to medium, gray; trace of silt; trace of clay, gray-white. (Split spoon).
45	50	Sand, very fine to fine, buff and gray; some white, red and yellow sandy clay.
		Discharge = Grayish-yellowish buff. (Bailer sample).
50	52	Sand, fine, some medium; trace of silt; trace of clay, gray-white; no odor. (Split spoon).
50	55	Clayey sand; sand, very fine to fine, gray, with some white clay with little red and yellow streaks.
		Discharge = Buff yellow. (Bailer sample).
55	60	Clayey sand; sand, very fine to fine, gray, with some white clay; trace streaks of yellow clayey sand and iron oxide spots.
		Discharge = Buff yellow.
60	65	Sand, very fine, tan; some grayish-white clay with little yellow clay, few sandstone fragments, trace of iron oxide. Grades to very fine, tan sand.

Discharge = Buff brown.

OWNER Whiteman, Osterman & Hanna, Former OCC Ruco Division, Hicksville, New YorkWELL NO. Site B


PAGE 4 OF 4 PAGES

DEPTH IN FEET FROM TO		DESCRIPTION
65	72	Sand, very fine, tan with little brown silt and trace of muscovite; some thin black and gray clay layers interbedded with gray and little orange (iron oxide) clayey sand.
		Discharge = Buff brown.
72	78	Sand, very fine to fine, orange; little brown silt, trace muscovite.
		Discharge = orange.
78	84	Clayey sand, very fine, gray and orange; trace of very fine, black sand and muscovite. Discharge grades from buff to gray-brown.
84	88	Sand, very fine, gray-tan; some gray-tan silt.
		Discharge = Grayish-tan.
90	94	Sand, very fine, gray-tan; some gray-tan silt.
		Discharge = Gray-tan.
96	104	Sand, very fine, buff; little buff silt.
		Discharge = tan.
	104.5	Bottom of borehole.

HKR 001 1288

WHITEMAN, OSTERMAN & HANNA
FORMER OCC PLANTSITE
HICKSVILLE, NEW YORK

CONSTRUCTION
OF MONITOR WELLS AT SITE B



* ALL CASINGS PULLED
DURING WELL INSTALLATION

LEGGETTE, BRASHEARS & GRAHAM, INC.

HKR 001 1289

GEOPHYSICAL WELL LOG

LEGGETTE, BRASHEARS & GRAHAM
CONSULTING GROUND-WATER GEOLOGISTS
72 DANBURY ROAD
WILTON, CT. 06897

OWNER Whiteman, Osterman & Hanna
LOCATION Former Occidental Chemical Corporation
Plantsite, Hicksville, New York
WELL NO. B
DRILLING METHOD Cable tool
DEPTH DRILLED 104 feet
DEPTH LOGGED 104 feet
DEPTH SCALE 20 feet/inch
LOGGED BY M. Susca and C. Fricke



DATE September 9, 1983
DRILLER R. H. Lauman & Associates, Inc.
REFERENCE POINT Grade
ELEVATION 130.5 feet above mean sea level
CASING 70 feet of 8 inch; 104 feet of 6 inch
HOLE DIAMETER 6-inch to 104 feet
REMARKS Static water level about 54.7 feet
below grade.

GAMMA RAY

Scale: 5 counts/second/inch
Time Constant: 3 seconds
Logging Rate: 25 feet/minute

Geol-
ogist's
Log

Increasing Radiation ➔



LEGGETTE, BRASHEARS & GRAHAM, INC. CONSULTING GROUND-WATER GEOLOGISTS

72 DANBURY ROAD
WILTON, CT. 06897

OWNER W. J. Ostrerman, Ostrerman & Hanna
Former OCC Ruco Division
Ricksville, New York

WELL NO. Site C

DATE 09/10/83 PAGE 1 OF 4 PAGES

		DEPTH IN FEET		DESCRIPTION
		FROM	TO	
LOCATION	Behind building 2	4	8	Cobbles, round, multicolored and very coarse to
	near shallow sump			very fine, subangular to round, multi-
DATE COMPLETED	September 23, 1983			colored gravel; some very coarse to very
DRILLING COMPANY	R. H. Lauman & Associates, Inc.			fine, tan sand.
DRILLING METHOD	Cable Tool			Discharge = Muddy tan.
SAMPLING METHOD	Bailer and split spoon	8	15	Sand, very coarse to very fine, tan and very
SAMPLES EXAMINED BY	C. Fricke			coarse to very fine, subangular to round,
REFERENCE POINT	Land surface			multicolored gravel; little very fine,
ELEVATION OF R.P.	133.3 ft. above MSL			multicolored cobble.
	C-1 135.62 ft. MSL			
	C-2 135.60 ft. MSL			
WELL CONSTRUCTION	wire-wrapped			Discharge = Muddy tan.
SCREEN TYPE	stainless steel			
DIAM.	2-inch	15	20	Gravel, very fine, angular, multicolored, and
	SLOT NO. 10			very fine to medium, tan sand; some rounded,
SETTING	50 to 70 ft.;			multicolored cobbles and coarse, rounded
	114 to 124 ft.			to subangular multicolored gravel.
GRAVEL PACK SIZE	Grade 1			Discharge = Muddy tan.
	New Jersey*			Sand, very fine to medium, tan and very fine
CASING	2-inch			angular multicolored gravel; some medium,
	stainless steel			subangular, multicolored gravel and coarse,
DEVELOPMENT	C-1 11 hrs. airlift			tan sand; little multicolored quartz
	4 1/2 hrs. bailer			cobbles, trace silt.
	C-2 6 1/2 hrs. airlift	20	25	Discharge = Cloudy tan.
PUMPING TEST	None			Sand, very fine to coarse, tan and very fine to
DATE				fine rounded multicolored, gravel; trace
DURATION				brown silt.
STATIC WATER LEVEL	C-1 78.68 ft. MSL			Discharge: Cloudy brown.
	C-2 77.69 ft. MSL			
PUMPING WATER LEVEL				
YIELD	C-1 1 gpm			
	C-2 6 gpm			
REMARKS:	Portland cement -	25	30	
	Deep zone: 74-103			
	Shallow zone: 42.5-grade			
	*Gravel pack setting -			
	Deep zone: 103-124			
	Shallow zone: 74-42.5			

HKR 001 1291

DEPTH IN FEET FROM TO		DESCRIPTION
30	35	Sand, very fine, some very coarse, tan and very fine to fine rounded to subangular, multicolored gravel; trace brown silt.
		Discharge = Muddy brown.
35	38	Sand, very fine to very coarse tan and very fine to medium, subangular to angular, multicolored gravel; some angular oxidized sandstone fragments, little brown silt.
		Discharge = Muddy orange-brown.
38	40	Gravel, very fine to medium, angular, multicolored, and very coarse, tan sand; some oxidized sandstone nodules, little silt.
		Discharge = Orange-brown.
40	45	Gravel, very fine to fine, subangular to angular, multicolored and very fine to very coarse, tan sand; some oxidized sandstone nodules; little silt.
		Discharge = Muddy brown.
45	50	Sand, very fine to fine, angular tan; little brown silt and 1-inch to 1 1/2-inch layers of very fine to fine orange clayey sand with 1/8-inch layer oxidized sandstone interbedded, trace very fine sub-angular white gravel.
		Discharge = Buff-brown.
	50	Sand, coarse to very fine, gray; some gray and black (oily sheen) clayey sand; mild odor.
		Discharge = Gray.
50	55	Sand, very coarse to very fine, orangish-tan; some orange, gray, white and red interbedded clayey sand and sandy clay.
		Discharge = Muddy brown.


DEPTH IN FEET FROM TO		DESCRIPTION
	55A	Sand, medium to very fine, gray; some gray, little yellow and trace red clay and sandy clay interbedded with white and black clayey sand; fishy odor.
		Discharge = Gray.
	55B	Sand, coarse to very fine, gray and black, gray, and red, some yellowish-tan interbedded sandy clays.
		Discharge = Gray.
55	60	Clay, and sandy clay, gray, yellow, black, white and orangish-red, interbedded; some fine to very fine gray sand; chemical odor.
		Discharge = Gray.
60	65	Sand, very fine, some very coarse and gray; little (interbedded) gray and black clay with yellow sandy clay.
		Discharge = Gray.
65	70	Sandy, very fine to fine tan and interbedded white, yellow, red, orange and trace pink, clay.
		Discharge = Grayish-tan.
70	80	Clay, gray; little very fine, gray clayey sand; trace oxidized sandstone nodules.
		Discharge = Gray.
80	85	Clay, gray; some orange, red and gray sandy clay, few oxidized sandstone nodules.
		Discharge = Gray-tan.
85	90	Sandy clay, very fine sand, buff brown with gray clay; trace nodules of sandstone.
		Discharge = Buff-brown.

PAGE 4 OF 4 PAGES

HKR 001 1294

WHITEMAN, OSTERMAN & HANNA
FORMER OCC PLANTSITE
HICKSVILLE, NEW YORK

CONSTRUCTION
OF MONITOR WELLS AT SITE C



* ALL CASINGS PULLED
DURING WELL INSTALLATION

LEGGETTE, BRASHEARS & GRAHAM, INC.

HKR 001 1295

WELL LOG

LEGGETTE, BRASHEARS & GRAHAM, INC.
CONSULTING GROUND-WATER GEOLOGISTS
72 DANBURY ROAD
WILTON, CT. 06897

OWNER Whiteman, Osterman & Hanna
Former OCC Ruco Division
Hicksville, New York

WELL NO. Test Boring C

DATE 1/13/84 PAGE 1 OF 2 PAGES

		DEPTH IN FEET		DESCRIPTION
		FROM	TO	
LOCATION	In shallow sump	0	2	Sand, very fine to medium, white and brown.
	north of building 2.			(Split spoon).
DATE COMPLETED	July 8, 1983	0	5	Sand, very coarse, tan; gravel, medium to coarse,
DRILLING COMPANY	R.H. Lauman & Associates, Inc.			angular to subangular quartz; no odor.
DRILLING METHOD	Cable tool - 6 inch			(Bailer sample).
	Split Spoon and Bailer.	5	7	Sand, fine to very coarse, brown; gravel fine to
SAMPLES EXAMINED BY	J. Naso			to medium; no odor. (Split spoon).
REFERENCE POINT	Sump bottom	10	12	Sand, medium to coarse, with some fine, tan;
ELEVATION OF R.P.	127.4 ft. above MSL			gravel, fine to very coarse; slight odor.
WELL CONSTRUCTION SCREEN TYPE	None			(Split spoon).
		10	15	Gravel, fine to very coarse; sand, fine to very
DIAM. _____ SLOT NO. _____				coarse, tan. (Bailer sample).
SETTING _____				
GRAVEL PACK SIZE _____		15	17	Gravel, fine to very coarse; large subangular
CASING _____				pebbles; sand, fine to very coarse; trace
DEVELOPMENT _____				of clay, gray. (Split spoon).
		15	20	Gravel, medium to very coarse; sand, fine to
PUMPING TEST				very coarse; trace of clay, white and gray.
DATE _____				(Bailer sample).
DURATION _____				
STATIC WATER LEVEL	48.6 ft. below grade	20	22	Sand, coarse to very coarse with some fine, tan;
PUMPING WATER LEVEL _____				gravel, fine to very coarse, angular to sub-
				angular quartz; trace of clay, red. (Split
YIELD _____				spoon).
REMARKS:	6-inch casing with-			
	drawn and test	25	27	Sand, very coarse to fine, tan; gravel, fine to
	boring grouted to			medium; trace of clay, red, white, gray.
	surface.			(Split spoon).

DEPTH IN FEET		DESCRIPTION
FROM	TO	
30	32	Sand, fine to coarse, brown; gravel fine to medium; iron oxide staining at 32 feet. (Split spoon).
30	35	Gravel, fine to very coarse, angular to subangular quartz; sand, fine to very coarse; iron oxide staining. (Bailer sample).
35	37	Sand, fine to medium, tan to white; gravel, fine to coarse; brown; no odor. (Split spoon).
35	40	Sand, medium to very coarse with some fine; tan. (Bailer sample).
40	42	Sand, fine to coarse, tan to gray; trace of clay, gray. (Split spoon).
40	45	Sand, fine to medium, with some very fine, tan. (Bailer sample).
45	47	Sand, fine to medium, with some very fine, tan; trace of clay, gray; no odor. (Split spoon).
47	50	Sand, medium to coarse, some fine, gray; some gravel; pieces of clay, brown.
50	52	Top 6 inches: Sand, very fine to medium, with some coarse, light gray; streaks of clay, red, gray, tan.
		Bottom 6 inches: Sand, very fine to medium, dark gray; trace of clay and silt, gray. (Split spoon).
52	54	Sand, very fine to medium, gray-green; clay, white, gray, yellow. (Split spoon).

HKR
001

HKR 001 1297

WELL LOG

LEGGETTE, BRASHEARS & GRAHAM, INC.
CONSULTING GROUND-WATER GEOLOGISTS

72 DANBURY ROAD
WILTON, CT. 06897

OWNER Whitman, Osterman & Hanna
Former OCC Ruco Division
Hicksville, New York

WELL NO. Site D

DATE 08/11/83 PAGE 1 OF 3 PAGES

	DEPTH IN FEET		DESCRIPTION
	FROM	TO	
LOCATION	North of fire water tanks, 30 feet from fence		4 foot topsoil.
			4-inch layer latex.
DATE COMPLETED	August 16, 1983		Sand, silt, stones and gravel, tan.
DRILLING COMPANY	R. H. Lauman & Associates, Inc.		(Above material from shoveled hole).
DRILLING METHOD	2	5	Sand, fine to coarse, tan; stones, gravel, and
SAMPLING METHOD	Split Spoon & Bailer		silt; some gray silty clay soil. (Bailer
SAMPLES EXAMINED BY	R. Lamonica		sample).
REFERENCE POINT	Grade 130.1 ft. above MSL	5 7	Sand, fine to coarse, tan, stones, gravel and
ELEVATION OF R.P.	D-1 132.37 ft. MSL		
	D-2 132.22 ft. MSL		silt; no odor; grades from tan to redder
WELL CONSTRUCTION	wire-wrapped		
SCREEN TYPE	stainless steel		tan. (Split spoon).
DIAM.	2-inch	5 10	Stones; gravel, fine to coarse, tan sand and tan
	SLOT NO. 10		
	86 to 91 ft.;		silt. (Bailer sample).
SETTING	45 to 65 ft.		
GRAVEL PACK SIZE	Grade 1	10 12	Gravel, and fine to coarse, tan sand; trace silt;
	New Jersey*		
CASING	2-inch		trace gray clay at tip of both spoons.
	stainless steel		
DEVELOPMENT	D-1 2 hrs. airlift		(Split spoon).
	13 hrs. bailer		
	D-2 4 hrs. airlift	10 15	Gravel, stones, and tan sand; trace silt.
PUMPING TEST	None		(Bailer sample).
DATE			
DURATION	15	17	Sand, fine to coarse, tan; gravel, and stones;
STATIC WATER LEVEL	D-1 77.64 ft. MSL		trace silt. (Split spoon).
	D-2 77.48 ft. MSL		
PUMPING WATER LEVEL	17	20	Gravel, stones, and fine to coarse, tan sand; no
	D-1 1 gpm		odor. (Bailer sample).
YIELD	D-2 4.5 gpm		
REMARKS:	Cement -	20 22	Sand, fine to medium, some coarse tan, gravel,
	Deep zone: 81.5 to 65		
	Shallow zone: 41 to grade.		and stones; trace silt; no odor. (Split
			spoon).
	*Gravel pack settings -		
	Deep zone: 81.5 to 91		
	feet.		
	Shallow zone: 41 to		
	65 feet.		

OWNER Whiteman, Osterman & Hanna, Former OCC Buco Division, Hicksville, New YorkWELL NO. D

PAGE 2 OF 3 PAGES


DEPTH IN FEET FROM TO		DESCRIPTION
22	25	Gravel; fine to coarse, tan sand, and stones (iron oxide stains). (Bailer sample).
25	27	Gravel, sand, and stones. (Split spoon).
27	30	Gravel, stones, and fine to coarse sand; trace silt; layer of silty clay with sand and stones; 3 to 4-inch concretions of iron oxide and staining on quartz grains. (Bailer sample).
30	32	Sand, fine to coarse; trace gravel. (Split spoon).
32	35	Gravel; fine to very coarse tan sand, and stones; some iron oxide con- cretions, trace silt and mica; faint odor. (Bailer sample).
35	37	Top 7 inches: Gravel, and fine to coarse sand, with iron oxide concretions. Bottom 5 inches: Sand, fine to medium, tan with trace layer of red and white clay. (Split spoon).
35	37	Gravel, and fine to medium, tan sand, with trace layer of red and white clay, iron oxide concretions. (Bailer sample).
38	40	Sand, fine to coarse; trace gravel and pink clay. (Bailer sample).
40	42	Top 10 inches: Sand, fine to medium, tan; trace silt. Bottom 5 inches: Sand, fine to medium; trace silt and red clay; no odor. (Split spoon).
42	45	Sand, fine to medium; some red and white clayey sand, trace of silt and gravel; no odor. (Bailer sample).
45	47	Top 5 inches: Sand, fine to medium, some coarse; trace red silt. Bottom 5 inches: Sand, fine to medium, some coarse; trace of red silt and red clay in matrix. (Split spoon).

HKR 001 1299

DEPTH IN FEET FROM TO		DESCRIPTION
45	50	Sand, fine to medium, multicolored, and red, white and yellow clay, sandy clay and clayey sand. (Bailer sample).
50	52	Sand, fine to medium, tan, and red and white clayey sand, fine to medium, 1-inch streaks white sandy clay and clay; no odor. (Split spoon).
52	54	Sand, fine to medium, tan with gray, red and yellow sandy clay, clayey sand and solid clay streaks. (Bailer sample).
54	55	Sand, fine to medium, tan. (Bailer sample).
55	57	Sand, fine to medium, tan. (Split spoon).
57	60	Sand, fine to medium, tan; trace red clay. (Bailer sample).
60	62	Sand, fine to coarse, tan; some red clay. (Bailer sample).
62	64	Sand, fine to medium, tan; some gray clayey sand. (Bailer sample).
64	65	Sandy clay, light gray; some iron oxide and tan sand. (Bailer sample).
65	67	Sand, very fine to fine, light gray to buff white, and silt; trace gray clay. (Bailer sample).
67	73	Silt, and very fine, light gray to gray sand; trace yellow and gray clay. (Bailer sample).
73	77	Silt, yellow; very fine, gray sand, and gray and yellow clay. (Bailer sample).
77	80	Silty clay, gray, some yellow and tan. (Bailer sample).
80	85	Silty clay, gray, some yellow and tan. (Bailer sample).
85	87	Sand, very fine to medium, red to tan, and silt. (Split spoon).
85	90	Sand, very fine to medium, red to tan and silt. (Bailer sample).
90	95	Sand, very fine to coarse, tan, and red and gray clay. (Bailer sample).
95	100	Silty clay, reddish-brown; some very fine to medium sand.
	100	Bottom of borehole.

WHITEMAN, OSTERMAN & HANNA
FORMER OCC PLANTSITE
HICKSVILLE, NEW YORK

CONSTRUCTION
OF MONITOR WELLS AT SITE D



* ALL CASINGS PULLED
DURING WELL INSTALLATION

LEGGETTE, BRASHEARS & GRAHAM, INC.

HKR 001 1301

GEOPHYSICAL WELL LOG

LEGGETTE, BRASHEARS & GRAHAM
CONSULTING GROUND-WATER GEOLOGISTS
72 DANBURY ROAD
WILTON, CT. 06897

OWNER Whiteman, Osterman & Hanna
LOCATION Former OCC Ruco Division Plantsite
Hicksville, New York
WELL NO. 0
DRILLING METHOD Cable Tool
DEPTH DRILLED 91 feet
DEPTH LOGGED 91 feet
DEPTH SCALE 20 feet/inch
LOGGED BY John Naso, Jr.


DATE August 16, 1983
DRILLER R. H. Tauman & Associates, Inc.
REFERENCE POINT Grade
ELEVATION 130.1 feet above mean sea level
CASING 67 feet of 8-inch; 91 feet of 6-inch
HOLE DIAMETER 6-inch to 91 feet
REMARKS Static water level is about 55 feet
below grade.

GAMMA RAY

SCALE: 7.5 counts/second/inch
TIME CONSTANT: 5 seconds
LOGGING RATE: 25 feet/minute

Increasing Radiation →

Geol-
ogist's
Log



- CLAY
- SILT
- SAND, FINE
- SAND, MEDIUM
- SAND, COARSE
- GRAVEL
- COBBLE
- SCREEN SETTING

WELL LOG
LEGGETTE, BRASHEARS & GRAHAM, INC.
CONSULTING GROUND-WATER GEOLOGISTS

72 DANBURY ROAD
WILTON, CT. 06897

OWNER Whiteman, Osterman & Hanna
Former OCC Ruco Division
Hicksville, New York

WELL NO. Site E

DATE 06/23/83 PAGE 1 OF 4 PAGES

		DEPTH IN FEET		DESCRIPTION
		FROM	TO	
LOCATION	Between sump No. 3 and storage shed	.6	.6	Sand, very coarse to medium with some fine, tan; strong paint-like odor.
DATE COMPLETED	August 10, 1983	.6	2.0	Sand, medium to fine with some very fine, dark brown; very strong paint-like odor.
DRILLING COMPANY	R. H. Lauman & Associates, Inc.			
DRILLING METHOD	Cable Tool			(Above material from shoveled hole and
SAMPLING METHOD	Split Spoon & Bailer			split spoon (1.6 - 1.5)).
SAMPLES EXAMINED BY	R. Lamonica and J. Naso	2.0	4.0	Sand, medium to coarse, light tan, and medium
REFERENCE POINT	Grade 129.3 ft. above MSL			to coarse with some fine gravel. (Bailer
ELEVATION OF R.P.	E-1 131.96 ft. MSL E-2 131.68 ft. MSL			sample).
WELL CONSTRUCTION SCREEN TYPE	wire-wrapped stainless steel	4.0	5.0	Gravel, medium to coarse, and medium to very
DIAM.	2-inch			coarse, with some fine; tan and gray sand;
SETTING	46 - 66 ft.; 75 - 90 ft.			silt; rubber-like material, very strong
GRAVEL PACK SIZE	Grade 1 New Jersey*			odor. (Bailer sample).
CASING	2-inch stainless steel	5.0	6.5	Sand, coarse to very coarse, with some medium
DEVELOPMENT	E-1 14 hrs. bailer 8 hrs. bailer			and fine, light brown to tan; gravel, and
	E-2 6 hrs. airlift			silt. (Split spoon).
PUMPING TEST	None	6.5	10.0	Gravel, well-rounded; stones; and fine to very
DURATION				coarse, tan-brown sand. (Bailer sample).
STATIC WATER LEVEL	E-1 77.40 ft. MSL E-2 77.31 ft. MSL	10.0	11.5	Sand, fine to medium, some coarse, tan-brown;
PUMPING WATER LEVEL				gravel and small stones. (Split spoon).
YIELD	E-1 1 gpm E-2 2 gpm	11.5	15.0	Sand, fine to very coarse tan-brown; well-
REMARKS:	Cement - 90-103 feet			rounded, gravel and stones. (Bailer sample).
	71-65.75 feet 42.8-grade.	15.0	17.0	Sand, fine to coarse tan-brown; well-rounded,
	Sand pack - Deep zone: 90 to 71 feet.			gravel and stones, trace of white clay
	Shallow zone: 65.75 to 42.8 feet.			and silt. (Split spoon).

Stick-up -
Shallow: 2.7 feet.
Deep: 2.4 feet.

HKR 001 1303

OWNER

Whiteman, Osterman & Hanna, Former OCC Ruco Division, Hicksville, New Yo

WELL NO.

Site E

PAGE 2 OF 4 PAGES

DEPTH IN FEET FROM TO		DESCRIPTION
17.0	20.0	Stones, (1-inch to 3-inch), rounded gravel and fine to very coarse, tan, sand. (Bailer sample).
20.0	22.0	Gravel; well-rounded, quartzitic stones and fine to very coarse, brown sand. (Split spoon).
22.0	25.0	Gravel; well-rounded, quartzitic stones and fine to very coarse, brown sand. (Bailer sample).
25.0	27.0	Gravel; well-rounded, quartzitic stones and fine to very coarse, brown sand. (Split spoon).
27.0	30.0	Gravel, fine to very coarse; 1-inch rounded quartzitic pebbles and fine to very coarse, tan sand. Discharge = Orange-rust. (Bailer sample).
30.0	32.0	Sand, fine to very coarse, light tan to tan; trace white, red and gray clay and fine gravel. (Split spoon).
32.0	35.0	Sand, fine to very coarse, tan and fine to very coarse, subangular quartz gravel; rust. (Bailer sample).
35.0	37.0	Sand, very fine to coarse, and fine to medium, brown; gravel; changing to whitish-tan gravel at 36.7 feet; trace white and gray clay in tip sample. (Split spoon).
37.0	40.0	Sand, fine to very coarse, tan; brown to orange silt and fine, sub-angular quartz gravel; (Bailer sample). Discharge = orange-red.
40.0	42.0	Sand, fine to coarse, tan to light gray; trace gray clay. (Split spoon).
42.0	44.0	Sand, fine to very coarse, tan and light gray, and silt. (Bailer sample).
44.0	45.0	Sand, fine to medium, gray, and gray and yellow clay (dries to tan). (Bailer sample).

OWNER

Whiteman, Osterman & Hanna, Former OCC Ruco Division, Hicksville, New York

WELL NO.

Site E


PAGE 3 OF 4 PAGE:

DEPTH IN FEET FROM TO		DESCRIPTION
45.0	47.0	Sand, fine to medium, gray, angular to subangular; trace gray clay. (Split spoon).
47.0	48.0	Sand, fine to coarse, angular to subangular, gray; some gray and white clay. (Bailer sample).
48.0	50.0	Sand, fine to coarse, gray; some gray clay; oily sheen, very strong odor of oil and chemicals.
50.0	52.0	Sand, fine to medium, some coarse, gray; 1-inch lens gray clay; sheen and odor. (Split spoon). (Moved off-site July 1, 1983 - returned July 20, 1983).
50.5	52.5	Sand, fine to medium, gray and white banded; some clay and silt; top 1-inch oily with strong odor; sample color getting lighter with depth; odor throughout; dry. (Split spoon).
52.5	54.0	Sand, fine to medium, gray; some tan, plastic clay. (Bailer sample).
54.0	56.0	Sand, fine to medium, gray; some clay and silt. (Split spoon).
56.0	59.5	Sand, fine to medium, light gray, quartzitic; trace biotite mica; oily sheen and strong odor, which appears to be getting weaker with depth; occasional clay and silt lumps. (Bailer sample).
59.5	61.5	Sand, fine to medium, gray; trace silt and clay. (Split spoon).
61.5	64.0	Sand, medium to very coarse, some fine, gray; strong odor; no oily sheen
64.0	65.0	Sand, medium to very coarse, some fine, gray; few lumps gray clay and sandy clay. (Bailer sample).
65.0	70.0	Sand, fine to very coarse, gray; silt; fine gravel; slight odor. (Bailer sample).

HKR 001 1305

WHITEMAN, OSTERMAN & HANNA
FORMER OCC PLANTSITE
HICKSVILLE, NEW YORK

CONSTRUCTION
OF MONITOR WELLS AT SITE E



NOT TO SCALE

*ALL CASINGS PULLED
DURING WELL INSTALLATION

LEGGETTE, BRASHEARS & GRAHAM, INC.

HKR 001 1307

GEOPHYSICAL WELL LOG

LEGGETTE, BRASHEARS & GRAHAM
CONSULTING GROUND-WATER GEOLOGISTS
72 DANBURY ROAD
WILTON, CT. 06897

OWNER Whiteman, Osterman & Hanna
LOCATION Former OCC Ruco Division Plantsite
Hicksville, New York
WELL NO. E
DRILLING METHOD Cable Tool
DEPTH DRILLED 103.3 feet
DEPTH LOGGED 94 feet
DEPTH SCALE 20 feet/inch
LOGGED BY John Naso


DATE August 10, 1983
DRILLER R. H. Lauman & Associates, Inc.
REFERENCE POINT Grade
ELEVATION 129.3 feet above mean sea level
CASING 60 feet of 12-inch; 70 feet of 8-inch;
103.3 feet of 6-inch.
HOLE DIAMETER 6-inch to 103.3 feet
REMARKS Static water level about 54.5 feet
below grade.

GAMMA RAY

SCALE: 7.5 counts/second/inch
TIME CONSTANT: 5 seconds
LOGGING RATE: 25 feet per minute

Increasing Radiation →

Geol-
ogist's
Log



LEGGETTE, BRASHEARS & GRAHAM, INC.
CONSULTING GROUND-WATER GEOLOGISTS

72 DANBURY ROAD
WILTON, CT. 06897

OWNER Whiteman, Osterman & Hanna
Former OCC Ruco Division
Hicksville, New York

WELL NO. Site F

DATE 9/27/83 PAGE 1 OF 3 PAGES

		DEPTH IN FEET		DESCRIPTION
		FROM	TO	
LOCATION	South end of plant	Grade	0.5	Fill; stones, sand and silt.
	near sump No. 2 & railroad tracks.	0.5	1.5	Sand, silt and gravel; some stains.
DATE COMPLETED	September 27, 1983	1.5	5.0	Stones, gravel, fine to coarse sand and brown
	R. H. Lauman & Associates, Inc.			silt; no odor. (Bailer sample).
DRILLING METHOD	Cable Tool	5	7	Sand, fine to coarse; brown gravel and silt;
	Split spoon and Bailer			trace clay. (Split spoon).
SAMPLING METHOD	R. Lamonica & C. Fricke	5	10	Gravel; stones; fine to coarse, brown sand and
	Grade 129.8 ft. above MSL			brown silt; no odor. (Bailer sample).
REFERENCE POINT	F-1 131.79 ft. MSL	10	12	Gravel; fine to coarse sand, and brown to tan
	F-2 131.56 ft. MSL			
ELEVATION OF R.P.	Wire-wrapped			silt; trace white clay in tip of spoon.
	stainless steel			(Split spoon).
WELL CONSTRUCTION	2-inch slot 10	15	17	Sand, fine to coarse; gravel and brown silt.
	DIAM. SLOT NO. F-1 47.5-67.5 ft. bgl			(Split spoon).
SETTING	F-2 90-110 ft. bgl			Sand, fine to coarse; tan; gravel and stones.
	Grade 1 New Jersey			(Bailer sample).
GRAVEL PACK SIZE	2-inch stainless steel	20	22	Top 6 inches: Sand, fine to coarse, tan and
				gravel.
CASING	F-1 14 hrs. bailer			Middle 6 inches: Sand, fine to coarse;
	DEVELOPMENT 1 hr. airlift			brown silt and gravel.
PUMPING TEST	F-2 5 hrs. airlift			Bottom 6 inches: Sand, fine to medium; some
	None			tan to gray silt.
DATE	F-1 76.99 ft. MSL			(Split spoon).
	STATIC WATER LEVEL F-2 76.88 ft. MSL			Gravel, fine to very fine, some medium; multi-
PUMPING WATER LEVEL	F-1 1 gpm			colored and very coarse to coarse, some
	F-2 5 gpm			medium sand; trace brown silt and iron stain.
YIELD	Sand pack: 80.5-			
	111 ft.; 71-35 ft. bgl	20	25	
REMARKS:	Grout: 80.5-71 ft. bgl			
	35 ft.-grade.			

Discharge = muddy brown. (Bailer sample).

OWNER

Whiteman, Osterman & Hanna, Former OCC Ruco Division, Hicksville, New York

WELL NO.

Site F

PAGE 2 OF 3 PAGES

DEPTH IN FEET FROM TO		DESCRIPTION
25	30	Sand, medium to fine, some coarse, angular, tan; and very fine, some fine, multicolored, subangular gravel. (Bailer sample).
30	35	Sand, medium to coarse, some fine, tan; very fine to fine multicolored subangular gravel and iron oxide nodules; some iron oxide concretions and brown silt; trace subangular multicolored cobbles. Discharge = Orange-brown. (Bailer sample).
35	40	Sand, medium to coarse, some fine to very fine, tan to brown and multicolored fine gravel; some gray sandy clay; slight odor. (Bailer sample).
40	42	Clay, sandy, gray interbedded with fine gray clayey sand and thin (1/4-inch) band of iron oxide; slight odor. (Split spoon).
40	45	Clay, sandy, gray and gray silt; slight odor. (Bailer sample).
45	48	Silt; fine, with some medium and coarse sand; gray clay and iron oxide stains; slight odor. (Bailer sample).
48	50	Silt, olive with fine sand and trace clay interbedded with plastic gray clay and micaceous gray sandy clay; strong odor. (Bailer sample).
	51	Sand, fine to very coarse, silt and plastic gray clay; no odor. (Bailer sample).
51.5	53.5	Sand, fine, silty, brown-gray, and sandy, brown-gray silt; no odor. (Split spoon).
50	55	Sand, fine to very coarse and tan silt; layers of fine sand and olive-brown silt; trace gravel; some odor. (Bailer sample).
55	60	Sand, fine and tan silt; slight "sweet" odor. (Bailer sample).
55	58	Sand, fine to medium and tan silt; no odor (Bailer sample).
58	60	Sand, fine to medium; trace white-gray silt; no odor. (Bailer sample).

OWNER Whiteman, Osterman & Hanna, Former OCC Ruco , Hicksville, New York

WELL NO. Site F


PAGE 3 OF 3 PAGES

DEPTH IN FEET FROM TO		DESCRIPTION
60	62	Sand, fine to medium; trace white-gray silt, slight odor. (Bailer sample
62	64	Sand, fine to medium; white gray; trace silt; very strong odor; no oil.
		Discharge = Dark gray-brown. (Bailer sample).
64	65	Sand, fine to coarse; trace gray silt; strong odor, no oil; (Bailer
		sample).
	65	Sand, fine to coarse, olive silt and iron oxide concretions; strong odor.
		(Bailer sample).
65	67	Sand, fine to very coarse; fine gravel and olive silt; some gray clay
		and sandy gray clay; strong odor. (Bailer sample).
	68	Clay, sandy, gray and fine olive sand; strong odor (Bailer sample).
68	70	Clay, sandy and silty, gray; strong odor. (Bailer sample).
70	82	Sand, clayey and silty, fine, gray, some olive; strong odor.
		(Bailer sample).
82	84	Sand, silty, fine, olive and gray, runny; strong odor. (Bailer sample).
84	90	Sand, silty, fine, olive and gray, runny; strong odor. (Bailer sample).
90	95	Sand, very fine, subangular and gray silt; few biotite flakes; chemical
		odor. (Bailer sample).
95	100	Sand, very fine to fine subangular and gray silt; some muscovite, little
		tourmaline(?) (black particles); odor. (Bailer sample).
100	110	Sand, very fine to fine, subangular and gray silt; some muscovite and
		feldspar; little tourmaline(?) (black particles); strong odor in clay
		lumps. (Bailer sample).
110	113	Sand, medium. (Bailer sample).
	113	Clay, gray and tan, layers on bottom of bailer.
	113	Bottom of borehole.

HKR 001 1311

WHITEMAN, OSTERMAN & HANNA
FORMER OCC PLANTSITE
HICKSVILLE, NEW YORK

CONSTRUCTION
OF MONITOR WELLS AT SITE F



*ALL CASINGS PULLED
DURING WELL INSTALLATION

NOT TO SCALE

LEGGETTE, BRASHEARS & GRAHAM, INC.

HKR 001 1312

GEOPHYSICAL WELL LOG

LEGGETTE, BRASHEARS & GRAHAM
CONSULTING GROUND-WATER GEOLOGISTS
72 DANBURY ROAD
WILTON, CT. 06897

OWNER Whiteman, Osterman & Hanna
LOCATION Former OCC Ruco Division Plantsite
Hicksville, New York
WELL NO. F
DRILLING METHOD Cable Tool
DEPTH DRILLED 114 feet
DEPTH LOGGED 112 feet
DEPTH SCALE 20 feet/inch
LOGGED BY Cintra Fricke


DATE October 5, 1983
DRILLER R. H. Lauman & Associates, Inc.
REFERENCE POINT Land Surface
ELEVATION 129.8 feet above mean sea level
CASING 12-inch to 50 feet; 8-inch to 70 feet;
6-inch to 114 feet.
HOLE DIAMETER 6-inch (inner casing)
REMARKS Static water level is about 54 feet
below grade.

GAMMA RAY

SCALE: 10 counts/second/inch
TIME CONSTANT: 3 seconds
LOGGING RATE: 21 feet/minute

Increasing Radiation →

Geol-
ogist's
Log



LEGGETTE, BRASHEARS & GRAHAM, INC.
CONSULTING GROUND-WATER GEOLOGISTS

72 DANBURY ROAD
WILTON, CT. 06897

OWNER
Former OCC Ruco Division
Hicksville, New York

WELL NO. Test Boring F

DATE 1/16/84 PAGE 1 OF 2 PAGES

		DEPTH IN FEET		DESCRIPTION
		FROM	TO	
LOCATION	Bottom of sump no. 2 southern most corner of plant.			Top 1/4-inch of sump bottom is a dry gray filter cake; 1/4-inch to 1-inch is brown-stained
DATE COMPLETED	July 19, 1983			sand; 1-inch to 2-inches is clean sand and
DRIILLING COMPANY	R. H. Lauman & Associates, Inc.			gravel.
DRIILLING METHOD	Cable tool - 6 inch	1	2.5	Sand, fine to coarse; gravel and silt; brown;
SAMPLING METHOD	Split Spoon and Bailer.			(Top 6 inches stained dark, bottom has clean
SAMPLES EXAMINED BY	R. Lamonica & J. Naso			appearance); strong odor. (Split spoon).
REFERENCE POINT	Grade: (sump bottom)	0	11.5	Sand, fine to very coarse; gravel; stones (to
ELEVATION OF R.P.	113.8 ft. above MSL			3-inches); brown; slight odor. (Bailer
WELL CONSTRUCTION SCREEN TYPE	None			sample).
DIAM.	SLOT NO.	11.5	13.3	Sand, fine to coarse; gravel; trace of silt;
SETTING				brown; some black staining; mild odor.
GRAVEL PACK SIZE				(Split spoon).
CASING		13.5	15	Sand, fine to coarse; gravel; brown; very slight
DEVELOPMENT				odor. (Bailer sample).
		15	17	Sand, fine to coarse; with some brown silt and
PUMPING TEST				a trace of gravel; no odor. (Split spoon).
DATE		17	20	Sand, very fine to coarse; some gravel; discharge
DURATION	Approx. 39 ft. below grade.			is dark gray, getting darker with depth;
STATIC WATER LEVEL				black stones causing color.
PUMPING WATER LEVEL		20	22	Sand, fine to medium, and silt, with streaks of
YIELD	6 inch casing			gray clay; some odor. (Split spoon).
REMARKS:	removed and hole	22	25	Sand, very fine, gray, with gray silt and clay.
	grouted to surface.			(Bailer sample).

HKR 001 1314

Whiteman, Osterman & Hanna, Former OCC Ruco Division, Hicksville, New York

Test Boring F

PAGE 2 OF 2 PAGES

[illegible]

IKR 001 1315

APPENDIX 13

**Records of Water Withdrawals
From Ruco Wells**

HKR 001 1317

LEGGETTE, BRASHEARS & GRAHAM, INC.

Hooker RUCO DIVISION

NEW SOUTH ROAD, HICKSVILLE, NEW YORK 11802
PHONE (516) 931-8100 TWX 510 221-1871

M/A 1034 AH:hmc

January 18, 1972

Long Island Well Application No. W-1442
Hooker Chemical Corp./Ruco Division

New York State Department of Environmental Conservation
Region 1 Water Supply Management Unit
373 Maple Avenue
Westbury, New York 11590

Attention: Mr. Walter G. Waterman
Chief, Water Supply Management Unit

Gentlemen:

Please be advised that Well Application No. W-1442 has not been pumped since October 1970. We have no plans of using this well in the future except in an extreme emergency, such as prolonged town water supply failure.

Very truly yours,

A. Heuer
Maintenance Supervisor

*13 MM gal/mo
12 MM gal/mo
15 M gal/mo*

HKR 001 1318

New York State Department of Environmental Conservation

Region 1 Water Supply Management Unit
373 Maple Avenue
Westbury, New York 11590

Henry L. Brown
Commissioner

January 17, 1972

Long Island Well Application No. W-1442
Hooker Chemical Co.

Hooker Chemical Co.
New South Road
Hicksville, New York 11802

Attention Mr. A. Heuer, Maintenance Supervisor


Gentlemen:

Our present records indicate that you have failed to report well water pumpage for the months of April through December, 1971.

Please be advised that pumpage is to be reported each month to this Department.

You are requested to forward the delinquent reports to this office immediately and monthly thereafter.

Very truly yours



WALTER G. WATERMAN
Chief, Water Supply Management Unit

ASC:sm

HKR 001 1319

April 19, 1971

State of New York
Water Resources Commission
3703 Maple Avenue
Westbury, N.Y.

Re: Wells No. N3450, 5368, 5390

Gentlemen:

The water consumption of the three wells for the month of March, 1971, was:

Well No. N3450	-	Not Running
Well No. N5368	-	Not Running
Well No. N5390	-	Not Running

Very truly yours,

A. Hutter
Maintenance Supervisor

March 12, 1971

State of New York
Water Resources Commission
3703 Maple Avenue
Westbury, N.Y.

Re: Wells No. N3450, 5368, 5390

Gentlemen:

The water consumption of the three wells for the month of February, 1971, was:

Well No. N3450	-	Not Running
Well No. N5368	-	Not Running
Well No. N5390	-	Not Running

Very truly yours,

A. Heuer,
Maintenance Supervisor

HKR 001 1321

October 13, 1970

State of New York
Water Resources Commission
3703 Maple Avenue,
Westbury, N.Y.

Re: Well No. N3450, 5368, 5390

Gentlemen:

The water consumption of the three wells for the month of
September 1970, was:

Well No. N3450	Not Running
Well No. N5368	Not Running
Well No. N5390	Not Running

Very truly yours,

A. Hauer
Maintenance Supervisor

HKR 001 1322

September 3, 1970

State of New York
Water Resources Commission
3703 Maple Avenue,
Westbury, N.Y.

Re: Well No. N3450, 5368, 5390

Gentlemen:

The water consumption of the three wells for the month of August,
1970:

Well No. N-3540

Not Running

Well No. N-5368

Present Meter Reading - 359,725,700
Previous Meter Reading- 359,506,800
218,900

Well No. N-5390

Not Running

Very truly yours,

A. Hauer
Maintenance Supervisor

HKR 001 1323

August 6, 1970

State of New York
Water Resources Commission
3703 Maple Avenue,
Westbury, N.Y.

Re: Well No's N3450, 5368, 5390

Gentlemen:

The water consumption of the three wells for the months of June and July, 1970, was:

Well No. N3540

Not Running

Well No. N5368

Present Meter Reading - 359,506,800
Previous Meter Reading - 359,101,300
405,000

Well No. N5390

Not Running

Very truly yours,

A. Hauer
Maintenance Supervisor

HKR 001 1324

May 8, 1970

State of New York
Water Resources Commission
5703 Maple Avenue
Westbury, N.Y.

Re: Well No's. N3450, 5368, 5390

Gentlemen:

The water consumption of the three wells for the month of April, 1970 was:

Well No. N3540

Not Running

Well No. N5368

Present Meter Reading - 353,704,700
Previous Meter Reading - 353,295,100
409,600

Well No. N5390

Not Running

Very truly yours,

A. Heuer
Maintenance Supervisor

HKR 001 1325

June 9, 1970

State of New York
Water Resources Commission
3703 Maple Avenue
Westbury, N.Y.

Re: Well No's. N3450, 5368, 5390

Gentlemen:

The water consumption of the three wells for the month of May 1970 was:

Well No. N3540	Not Running
Well No. N5368	Present Meter Reading - 359,101,300 Previous Meter Reading - <u>358,704,700</u> 397,100
Well No. N5390	Not Running

Very truly yours,

A. Hauer
Maintenance Supervisor

HKR 001 1326

April 9, 1970

State of New York
Water Resources Commission
3703 Maple Avenue
Westbury, N.Y.

Re: Well No's. N3450, 5368, 5390

Gentlemen:

The water consumption of the three wells for the month of March, 1970 was:

Well No. N3540

Not Running

Well No. N5368

Present Meter Reading - 358,295,100

Previous Meter Reading - 357,766,300
523,300

Well No. N5390

Not Running

Very truly yours,

A. Heuer
Maintenance Supervisor

HKR 001 1327

HOOKEE RUCO DIVISION

NEW SOUTH ROAD, HICKSVILLE, NEW YORK 11802
PHONE (516) 931-8100 TWX 510 221-1871

March 6, 1970

State of New York
Water Resources Commission
3703 Maple Avenue
Westbury, N.Y.

Re: Well No's N3450, 5368, 5390

Gentlemen:

The water consumption of the three wells for the Month of February, 1970 was:

Well No. N3540

Not Running

Well No. N5368

Present Meter Reading - 357,766,300
Previous Meter Reading - 357,358,000
408,300

Well No. N5390

Not Running

Very truly yours,

A. Heuer
Maintenance Supervisor

HKR 001 1328

February 5, 1970

State of New York
Water Resources Commission
3703 Maple Avenue
Westbury, N.Y.

Re: Well No's N3450, 5368, 5390

Gentlemen:

The water consumption of the three wells for the month of January, 1970 was:

Well No. N3540

Not Running

Well No. N5368

Present Meter Reading - 357,353,000
Previous Meter Reading - 356,761,000
597,000

Well No. N5390

Not Running

Very truly yours,

A. Hauer
Maintenance Supervisor

HKR 001 1329

January 5, 1970

State of New York
Water Resources Commission
3703 Maple Ave.
Westbury, N.Y.

Re: Well No's N3450, 5368, 5390

Gentlemen:

The water consumption of the three wells for the month of
December, 1969 was:

Well No. N3450

Not Running

Well No. N5368

Present Meter Reading - 356,761,000
Previous Meter Reading - 356,155,900
605,100

Well No. N5390

Not Running

Very truly yours,

A. Heuer
Maintenance Supervisor

HKR 001 1330

December 2, 1969

State of New York
Water Resources Commission
3703 Maple Avenue
Westbury, N.Y.

Re: Well No.'s N3450, 5368, 5390

Gentlemen:

The water consumption of the three wells for the month of November, 1969 was:

Well No. N3450

Not Running

Well No. N5368

Present Meter Reading -	356,155,900
Previous Meter Reading -	<u>355,294,900</u>
	861,000

Well No. N5390

Not Running

Very truly yours,

A. Hauer
Maintenance Supervisor

AH/eb

November 7, 1969

State of New York
Water Resources Commission
3703 Maple Avenue
Westbury, N.Y.

Re: Well No.'s N3450, 5368, 5390

Gentlemen:

The water consumption of the three wells for the month of
October, 1969 was:

Well No. N3450	Not Running
Well No. N5368	Meter being repaired.
Well No. N5390	Not Running

Very truly yours,

A. Hauer
Maintenance Supervisor

AH/eb

October 8, 1969

State of New York
Water Resources Commission
3703 Maple Avenue
Westbury, N.Y.

Re: Well No.'s N3450, 5368, 5390

Gentlemen:

The water consumption of the three wells for the month of
September, 1969 was:

Well No. N3450

Not Running

Well No. N5368

Present Meter Reading - 355,294,900
Previous Meter Reading - 354,440,500
854,400

Well No. N5390

Not Running

Very truly yours,

A. Heuer
Maintenance Supervisor

AH/ab

September 3, 1969

State of New York
Water Resources Commission
3703 Maple Avenue
Westbury, N.Y.

Re: Well No.'s N3450, 5368, 5390

Gentlemen:

The water consumption of the three wells for the month of August, 1969 was:

Well No. N3450

Not Running

Well No. N5368

Present Meter Reading - 354,440,500
Previous Meter Reading - 353,587,200
253,300

Well No. N5390

Not Running

Very truly yours,

A. Hauer
Maintenance Supervisor

eb

HKR 001 1334

August 5, 1969

State of New York
Water Resources Commission
3703 Maple Avenue
Westbury, N.Y.

Re: Well No.'s N3450, 5368, 5390

Gentlemen:

The water consumption of the three wells for the
months of June and July 1969 was:

Well No. N3450	Not Running
Well No. N5368	Present Meter Reading - 353,587,200 Previous Meter Reading - 352,314,200 1,273,000
Well No. N5390	Not Running

Very truly yours,

A. Heuer
Maintenance Supervisor

AH/js

HKR 001 1335

June 5, 1969

State of New York
Water Resources Commission
3703 Maple Avenue
Westbury, N.Y.

Re: Well No.'s N3450, 5368, 5390

Gentlemen:

The water consumption of the three wells for the month of May, 1969,
was:

Well No. N3450

Not Running

Well No. N5363

Present Meter Reading -	352,314,200
Previous Meter Reading -	<u>351,511,500</u>
	802,700

Well No. N5390

Not Running

Very truly yours,

A. Heuer
Maintenance Supervisor

HKR 001 1336

May 2, 1969

State of New York
Water Resources Commission
3703 Maple Avenue
Westbury, N.Y.

Re: Well No.'s N3450, 5368, 5390

Gentlemen:

The water consumption of the three wells for the month of April, 1969
was:

Well No. N3450

Not Running

Well No. NS363

Present Meter Reading - 351,511,500
Previous Meter Reading - 350,791,000
720,500

Well No. NS390

Not Running

Very truly yours,

A. Heuer
Maintenance Supervisor

el.

HKR 001 1337

April 7, 1969

State of New York
Water Resources Commission
3703 Maple Avenue,
Westbury, N.Y.

Re: Well No.'s N3450, 5368, 5390

Gentlemen:

The water consumption of the three wells for the month of March, 1969
was:

Well No. N3450

Not Running

Well No. N5368

Present Meter Reading - 350,791,000
Previous Meter Reading - 349,801,900
939,100

Well No. N5390

Not Running

Very truly yours,

A. Heuer
Maintenance Supervisor

Al:/eb

HKR 001 1338

March 5, 1969

State of New York
Water Resources Commission
3703 Maple Avenue,
Westbury, N.Y.

Re: Well No.'s N3450, 5368, 5390

Gentlemen:

The water consumption of the three wells for the month of
February, 1969 was:

Well No. N3450	Not Running
Well No. N5368	Present Meter Reading - 349,801,900
	Previous Meter Reading - 349,094,900
	<u>717,000</u>
Well No. N5390	Not Running

Very truly yours,

A. Hauer
Maintenance Supervisor

Al/sb

HKR 001 1339

February 4, 1969

State of New York
Water Resources Commission
3703 Maple Avenue,
Westbury, N.Y.

Re: Well No.'s N3450, 5368, 5390

Gentlemen:

The water consumption of the three wells for the month of January, 1969 was:

Well No. N3450

Not Running

Well No. N5368

Present Meter Reading	-	349,094,900
Previous Meter Reading	-	<u>348,069,700</u>
		925,200

Well No. N5390

Not Running

Very truly yours,

A. Heuer
Maintenance Supervisor

AH/sb

HKR 001 1340

January 8, 1969

State of New York
Water Resources Commission
3703 Maple Avenue,
Westbury, N.Y.

Re: Well No.'s N3450, 5368, 5390

Gentlemen:

The water consumption of the three wells for the month of December, 1968 was:

Well No. N3450

Not Running

Well No. N5368

Present Meter Reading - 348,069,700 -
Previous Meter Reading - 347,012,400
1,057,300

Well No. N5390

Not Running

Very truly yours,

A. Heuer
Maintenance Supervisor

HKR 001 1341

December 6, 1968

State of New York
Water Resources Commission
3703 Maple Avenue,
Westbury, N.Y.

Re: Well No's N3450, 5368, 5390.

Gentlemen:

The water consumption of the three wells for the month of November,
1968 was:

Well No. N3450

Not running

Well No. N5368

Present Meter Reading	-	347,012,400
Previous Meter Reading	-	346,058,000
		<u>954,400</u>

Well No. N5390

Not running

Very truly yours,

A. Heuer
Maintenance Supervisor

HKR 001 1342

November 7, 1968

State of New York
Water Resources Commission
3703 Maple Avenue
Westbury, N.Y.

Re: Well No's N3450, 5368, 5390

Gentlemen:

The water consumption of the three wells for the month of
October, 1968 was:

Well No. N3450	Not Running
Well No. N5368	Present Meter Reading - 346,058,000
	Previous Meter Reading - 344,850,700
	<u>1,207,300</u>
Well No. N5390	Not Running

Very truly yours,

A. Heuer
Maintenance Supervisor

HKR 001 1343

October 1, 1968

State of New York
Water Resources Commission
3703 Maple Avenue
Westbury, N.Y.

Re: Well No's N3450, 5368, 5390

Gentlemen:

The water consumption of the three wells for the month of
September, 1968 was:

Well No. N3450

Not Running

Well No. N5368

Present Meter Reading - 344,850,700
Previous Meter Reading - 343,702,200
1,148,500

Well No. N5390

Not Running

Very truly yours,

A. Heuer
Maintenance Supervisor

HKR 001 1344

September 6, 1968

State of New York
Water Resources Commission
3703 Maple Avenue
Westbury, N.Y.

Re: Well No's N3450, 5368, 5390

Gentlemen:

The water consumption of the three wells for the month of
August, 1968 was

Well No. N3450

Not Running

Well No. N5368

Present Meter Reading -	343,702,200
Previous Meter Reading -	342,508,200
	<u>1,194,000</u>

Well No. N5390

Not Running

Very truly yours,

A. Heuer
Maintenance Supervisor

HKR 001 1345

August 9, 1968

State of New York
Water Resources Commission
3703 Maple Avenue
Westbury, N.Y.

Re: Well No's N3450, 5368, 5390

Gentlemen:

The water consumption of the three wells for the months of June and July, 1968 was:

Well No. N3450	Not Running
Well No. N5368	Present Meter Reading - 342,508,200
	Previous Meter Reading - <u>339,956,400</u>
	2,551,800
Well No. N5390	Not Running

Very truly yours,

A. Heuer
Maintenance Supervisor

HKR 001 1346

June 10, 1968

State of New York
Water Resources Commission
3703 Maple Avenue,
Westbury, N.Y.

Re: Well No's N3450, 5368, 5390

Gentlemen:

The water consumption of the three wells for the month of
May, 1968 was:

Well No. N3450	-	Not Running	
Well No. N5368	-	Present Meter Reading	- 339,956,400
		Previous Meter Reading	- 338,829,600
			<u>1,126,800</u>
Well No. N5390	-	Not Running	

Very truly yours,

A. F. Heuer
Maintenance Supervisor

AF/eb

HKR 001 1347

May 10, 1968.

State of New York
Water Resources Commission
3703 Maple Avenue,
Westbury, N.Y.

Re: Well No's N3450, 5368, 5390

Gentlemen:

The water consumption of the three wells for the month of
April, 1968 was:

Well No. N3450

Not Running

Well No. N5368

Present Meter Reading - 338,829,600
Previous Meter Reading - 337,884,700
844,900

Well No. N5390

Not Running

Very truly yours,

A. P. Heuer
Maintenance Supervisor

AF/ab

HKR 001 1348

April 2, 1968.

State of New York
Water Resources Commission
3703 Maple Avenue,
Westbury, New York.

Re: Wells No's. N3450, 5368, 5390

Gentlemen:

The water consumption of the three wells for the month of March, 1968 was:

Well No. N3450

Not Running

Well No. N5368

Present Meter Reading - 337,884,700
Previous Meter Reading - 337,060,200
824,500

Well No. N5390

Not Running

Very truly yours,

A. P. Heuer
Maintenance Supervisor

HKR 001 1349

March 7, 1968.

State of New York
Water Resources Commission
3703 Maple Avenue,
Westbury, N.Y.

Re: Well No.s N3450, 5368, 5390

Gentlemen:

The water consumption of the three wells for the month of
February, 1968 was:

Well No. N-3450

Not Running

Well No. N-5368

Present Meter Reading - 337,060,200
Previous Meter Reading - 536,263,900
796,300

Well No. N-5390

Not Running

Very truly yours

A. F. Heuer
Maintenance Supervisor

AF/eb

HKR 001 1350

February 5, 1968

State of New York
Water Resources Commission
3703 Maple Avenue,
Westbury, N.Y.

Re: Well No.s N3450, 5368, 5390

Gentlemen:

The water consumption of the three wells for the month of
January, 1968 was:

Well No. N-3450

Not Running

Well No. N5368

Present Meter Reading	336,263,900
Previous Meter Reading	<u>335,349,200</u>
	914,700

Well No. N5390

Not Running

Very truly yours,

A. P. Heuer
Maintenance Supervisor

AF/eb

January 8, 1968

State of New York
Water Resources Commission
3703 Maple Avenue
Westbury, New York.

Re: Wells No's N3450, 5368, 5390

Gentlemen:

The water consumption of the three wells for the month of
December, 1967 was:

Well No. N3450	Not Running	
Well No. N5368	Present Meter Reading	335,349,200
	Previous Meter Reading	<u>354,463,100</u>
		886,100
Well No. N5390	Not Running	

Very truly yours,

A. F. Heuer
Maintenance Supervisor

AF/eb

HKR 001 1352

December 4, 1967.

State of New York
Water Resources Commission
375 Maple Ave.,
Westbury, New York.

Re: Wells No's N3450, 5368, 5390

Gentlemen:

The water consumption of the three wells for the month of
November, 1967 was:

Well No. N3450	Not Running
Well No. N5368	Present Meter Reading 334,463,100
	Previous Meter Reading 333,484,700
	<u>978,400</u>
Well No. N5390	No Running

Very truly yours,

A. F. Hauer
Maintenance Supervisor

Al/eb

HKR 001 1353

November 6, 1967.

State of New York
Water Resources Commission
373 Maple Avenue
Westbury, New York.

Re: Wells No's. N3450, S368, S390

Gentlemen:

The water consumption of the three wells for the month of
October, 1967 was:

Well No. N3450

Not Running

Well No. N5368

Present Meter Reading: 333,484,700
Previous Meter Reading: 332,652,500
832,200

Well No. N5390

Not Running

Very truly yours,

A. P. Heuer
Maintenance Supervisor

AFH/eb

HKR 001 1354

October 11, 1967.

State of New York
Water Resources Commission
375 Maple Avenue
Westbury, New York.

Re: Wells No's. NS450, NS308, NS390

Gentlemen:

The water consumption of the three wells for the month of
~~September~~, 1967 was:

Well No. NS450

No Running

Well No. NS308

Present Meter Reading 332,652,540

Previous Meter Reading 331,200,640
1,451,900

Well No. NS390

No Running

Very truly yours,

A. P. Heuer
Maintenance Supervisor

AHH/CO

September 8, 1967.

State of New York
Water Resources Commission
373 Maple Avenue
Westbury, New York.

Re: Wells No's. N3450, 5368, 5390

Gentlemen:

The water consumption of the three wells for the months of
June, July and August, 1967 was:

Well No. N3450

Not Running

Well No. N5368

Present Meter Reading 331,200,600
Previous Meter Reading 326,513,600
4,687,000

Well No. N5390

Not Running

Very truly yours,

A. P. Heuer
Maintenance Supervisor

AFH/al

HKR 001 1356

June 6, 1967

State of New York
Water Resources Commission
373 Maple Avenue
Westbury, New York

Re: Wells #N3450, 5368, 5390

Gentlemen:

The water consumption of the three wells for the month of May,
1967, was:

Well #N3450

Not Running

Well #N5368

Present Meter Reading 326,513,600

Previous Meter Reading 325,171,700
1,341,900

Well #N5390 -

Not Running

Very truly yours,

A. F. Heuer
Maintenance Supervisor

AHH/vgd

00000000
00000000

207 207 00
15. 15. 01

HKR 001 1357

May 5, 1967

State of New York
Water Resources Commission
373 Maple Avenue
Westbury, New York

Re: Wells #N3450, 5368, 5390

Gentlemen:

The water consumption of the three wells for the month of
April, 1967, was:

Well #N3450

Not Running

Well #N5368

Present Meter Reading	325,171,700
Previous Meter Reading	<u>323,949,600</u>
	1,222,100

Well #N5390

Not Running

Very truly yours,

A. Heuer
Maintenance Supervisor

AFH/vgd

HKR 001 1358

April 3, 1967

State of New York
Water Resources Commission
373 Maple Avenue
Westbury, New York

Re: Well 7N3450, 5368, 5390

Gentlemen:

The water consumption of the three wells for the month of March, 1967, was:

Well #N3450 Not Running

Well #N5368

Present Meter Reading	323,949,600
Previous " "	322,748,100
	<u>1,201,500</u>

Well #N5390 Not Running

Very truly yours,

A. F. Heuer
Maintenance Supervisor

APH/vd

HKR 001 1359

March 1, 1967

State of New York
Water Resources Commission
373 Maple Avenue
Westbury, New York

Re: Well #N3450, 5368, 5390

Gentlemen:

The water consumption of the three wells for the month of February, 1967, was:

Well #N3450 Not Running

Well #N5368

Present Meter Reading	322,748,100
Previous " "	<u>321,619,600</u>
	1,128,500

Well #N5390 Not Running

Very truly yours,

A. F. Heuer
Maintenance Supervisor

AFH/vd

HKR 001 1360

February 6, 1967

State Of New York
Water Resources Commission
373 Maple Avenue
Westbury, New York

Re: Well #N3450, 5368, 5390

Gentlemen:

The water consumption of the three wells for the month of January, 1967, was:

Well #N3450

Not Running

Well #N5368

Present Meter Reading
Previous Meter Reading

321,619,600
320,280,500
1,339,100

Well #N5390

Not Running

Very truly yours,

A. P. Hauer
Maintenance Supervisor

AFH/vd

HKR 001 1361

January 9, 1967

State of New York
Water Resources Commission
373 Maple Avenue
Westbury, New York

Re: Well #N3450, 5368, 5390

Gentlemen:

The water consumption of the three wells for the month
of December, 1966, was:

Well #N3450	Not Running
Well #N5368	
Present Meter Reading	320,280,500
Previous Meter Reading	<u>318,993,700</u>
	1,286,800

Well #N5390

Not Running

Very truly yours,

A. F. Heuer
Maintenance Supervisor

AFH/vd

December 7, 1966

State of New York
Water Resources Commission
373 Maple Avenue
Westbury, New York

Re: Well #H3450, 5368, 5390

Gentlemen:

The water consumption of the three wells for the month of November, 1966, was:

Well #3450 Not Running

Well #H5368

Present Meter Reading	318,993,700
Previous Meter Reading	<u>317,884,900</u>
	1,108,800

Well #H5390 Not Running

Very truly yours,

A. F. Heuer
Maintenance Supervisor

AFH/vd

HKR 001 1363

November 8, 1966

State of New York
Water Resources Commission
373 Maple Avenue
Westbury, New York

Gentlemen:

Re: Well #N3450, 5368, 5390

The water consumption of the above three wells for the month of October, 1966, was:

Well #N3450 Not Running

Well #N5368

Present Meter Reading	317,884,900
Previous Meter Reading	<u>316,729,700</u>
	1,155,200

Well #N5390 Not running

Very truly yours,

A. P. Heuer
Master Mechanic

AFH/vd

HKR 001 1364

October 5, 1966

State of New York
Water Resources Commission
373 Maple Avenue
Westbury, New York

Re: Well #N3450, 5368, 5390

Gentlemen:

The water consumption of the above three wells for the month of September, 1966, was:

Well #N3450

Not Running

Well #N5368

Present Meter Reading
Previous Meter Reading

316,729,700 gallons
315,175,200 gallons
1,554,500 gallons

Well #N5390

Not Running

Very truly yours,

A. P. Heuer
Master Mechanic

AFH/vd

HKR 001 1365

September 2, 1966

State of New York
Water Resources Commission
373 Maple Avenue
Wascburg, New York

Gentlemen:

Re Well #N3450, Well #N5368, Well #N5390

The water consumption of the above three wells for the month of August, 1966 was:

Well #N3450

Not Running

Well #N5368

Present Meter Reading
Previous Meter Reading

315,175,200 gallons
312,450,800 gallons
2,724,400 gallons

Well #N5390

Not Running

Very truly yours,

A. F. Heuer
Master Mechanic

A2H:ma

HKR 001 1366

August 5, 1966

State of New York
Water Resources Commission
373 Maple Avenue
Westbury, New York

Gentlemen:

Re Well #W3450, Well #W5368, Well #W5390

The water consumption of the above three wells for the month of June, 1966, was:

Well #W3450

Not Running

Well #W5368

Present Meter Reading
Previous Meter Reading

312,367,600 gallons -
310,522,800 gallons
1,744,800 gallons

Well #W5390

Not Running

The water consumption of the above three wells for the month of July, 1966, was:

Well #W3450

Not Running

Well #W5368

Present Meter Reading
Previous Meter Reading

312,450,800 gallons
312,367,600 gallons
83,200 gallons

Very truly yours,

A. P. Bauer
Master Mechanic

AZL:ms

HKR 001 1367

June 1, 1966

State of New York
Water Resources Commission
373 Maple Avenue
Westbury, New York

Gentlemen:

RX Well #N3450, Well #N5368, Well #N5390

The water consumption of the above three wells for the month of May, 1966, was:

Well #N3450

Not Running

Well #N5368

Present Meter Reading
Previous Meter Reading

310,622,800 gallons -
309,635,000 gallons
987,800 gallons

Well #N5390

Not Running

Very truly yours,

A. F. Hauer
Master Mechanic

A7H:ms

HKR 001 1368

May 2, 1966

State of New York
Water Resources Commission
373 Maple Avenue
Westbury, New York

Gentlemen:

Re Well #N3450, Well #N5368, Well #N5390

The water consumption of the above three wells for the month of April, 1966, was:

Well #N3450

Not Running

Well #N5368

Present Meter Reading
Previous Meter Reading

309,635,000 gallons
308,659,900 gallons
975,100 gallons

Well #N5390

Not Running

Very truly yours,

A. F. Bauer
Master Mechanic

AFB:ms

HKR 001 1369

April 4, 1966
E-02-66

State of New York
Water Resources Commission
373 Maple Avenue
Westbury, New York

Gentlemen:

Re Well #3450, Well #N5368, Well #N5390

The water consumption of the above three wells for the month of March, 1966, was:

Well #N3450

Not Running

Well #N5368

Present Meter Reading
Previous Meter Reading

308,659,900 gallons
307,721,000 gallons
938,900 gallons

Well #N5390

Not Running

Very truly yours,

A. F. Hauer,
Master Mechanic

AJH:ms

March 1, 1966

State of New York
Water Resources Commission
373 Maple Avenue
Westbury, New York

Gentlemen:

Re Well #N3450, Well #N5368, Well #N5390

The water consumption of the above three wells for the month of February, 1966, was:

Well #N3450

Not Running

Well #N5368

Present Meter Reading
Previous Meter Reading

307,721,000 gallons
306,349,300 gallons
871,700 gallons

Well #N5390

Not Running

Very truly yours,

A. F. Hauer,
Master Mechanic

AFH:na

HKR 001 1371

February 3, 1966

89-10

Februar /

State of New York
Water Resources Commission
373 Maple Avenue
Westbury, New York

Gentlemen:

Reference: Well #N3450, Well #N5368, & Well #N5390

The water consumption of the above three wells for the month of January, 1966 was as follows:

Well #N3450

Meter Reading January 1	47,600 gal.
Meter Reading February 1	<u>47,600 gal.</u>

Well #N5368

Meter Reading February 1	306,849,300 gal.
Meter Reading January 1	<u>306,067,300 gal.</u>

782,100 gal.

Well #N5390

Meter Reading January 1	87,136,300 gal.
Meter Reading February 1	<u>87,136,300 gal.</u>

Sincerely,

August F. Bauer
Master Mechanic

P. DeRiaz _____
mc

HKR 001 1372

January 3, 1966
E-1-6-AH-bs

State of New York
Water Resources Commission
373 Maple Avenue
Westbury, New York

Gentlemen:

Reference: Well #N3450, Well #N5368, and Well #N5390

The water consumption of the above three wells for the month of December, 1965 was as follows:

Well #N3450

Meter Reading December 1
Meter Reading January 1

47,600 gal.
47,600 gal.

Well #N5368

Meter Reading December 1
Meter Reading January 1

305,219,500 gal.
306,067,200 gal.
847,700 gallons

Well #N5390

Meter Reading December 1
Meter Reading January 1

87,136,300 gal.
87,136,300 gal.

Sincerely yours,

[Signature]
August F. Hauer
Master Mechanic

[Signature]
P. DeVries

DATE	# 1 #N3450	# 2 #N5368	# 3 #M5390
6/60	not running	Cons. 1,744,800 M.R. 312,367,600	not running
7/66	not running	Cons. 83,200 M.R. 312,450,800	not running
8/66	not running	Cons. 2,724,400 M.R. 315,175,200	not running
9/66	not running	Cons. 1,554,500 M.R. 316,729,700	not running
10/66	not running	Cons. 1,155,200 M.R. 317,334,900	not running
11/66	not running	Cons. 1,108,800 M. R. 318,993,700	not running
12/66	not running	Cons. 1,286,800 M. R. 320,280,500	not running
1/67	not running	Cons. 1,339,100 M. R. 321,619,600	not running
2/67	not running b	Cons. 1,128,500 M. R. 322,748,100	not running
3/67	not running	M. R. 323,949,600 Cons. 1,201,500	not running
4/67	not running	M. R. 325,171,700 Cons. 1,222,100	not running
7/67	not running	M. R. 281,127,100 Cons. 297,044,600	not running

1/1/68	M.R. 335,349,200
1/1/69	" 348,069,200
7/1/69	" 351,511,500

Cons. * Consumption
M.R. - Meter Reading

HKR 001 1374

DATE	#N3450	#N5363	#N5390
10/64		803,800 gallons	564,400 gallons
11/64		694,000 gallons	1,528,000 gallons
12/64		854,700 gallons	1,486,900 gallons
1/65		938,700 gallons	1,653,100 gallons
2/65		837,000 gallons	728,000 gallons
3/65		1,062,600 gallons	500 gallons
4/1		1,146,300 gallons	4,400 gallons
6/1/65	not running	1,255,600 gallons	not running
8/65 (May, June, July, August)	not running	3,163,000 gallons	not running
9/65	not running	1,744,300 gallons	not running
10/65	<u>M.R.</u> 47,600 Nov. 1 <u>Cons.</u> not running	<u>M.R.</u> 304,399,600 Nov. 1 <u>cons.</u> 916,300	<u>M.R.</u> 87,136,300 <u>Cons.</u> 4,400 not running
11/65	<u>M. R.</u> <u>Cons.</u> not running	<u>Cons.</u> 819,900 <u>M. R.</u> 305,219,500	<u>Cons.</u> <u>M. R.</u> not running
12/65	<u>M. R.</u> <u>Cons.</u> not running	<u>Cons.</u> 847,700 <u>M.R.</u> 306,067,200 <u>Cons.</u>	<u>Cons.</u> <u>M. R.</u> not running
1/66	<u>Cons.</u> <u>M. R.</u> not running	<u>Cons.</u> 7,82,100 <u>M.R.</u> 306,849,300	<u>Cons.</u> <u>M.R.</u> Not running
2/66		<u>Cons.</u> 871,700 <u>M.R.</u> 307,721,000	
3/66		<u>Cons.</u> 938,900 <u>M. R.</u> 308,659,900	
4/66		<u>Cons.</u> 975,000 <u>M.R.</u> 309,635,000	
5/66		<u>Cons.</u> 987,800 <u>M.R.</u> 310,622,800	

M. R. = Meter Reading
Cons. = Consumption

WELL WATER CONSUMPTION

Mc O'Reilly

<u>DATE</u>	<u>#W53450</u>	<u>#W5368</u>	<u>#W5390</u>
10/62		409,000 gal	636,100 gal
11/62		378,700 gal	
12/62		379,800 gal	
1/63		476,100 gal	
2/63		353,400 gal	
3/63		505,500 gal	
4/63		653,800 gal	
5/63		975,600 gal	
6/63		616,200 gal	
7/63		1,493,400 gal	
8/63			
9/63 (combined reading)		2,131,300 gal	6,745,000 gal
10/63		969,500 gal	1,281,600 gal
11/63		986,400 gal	572,800 gal
12/63		929,300 gal	1,620,500 gal
1/64		906,700 gal	860,900 gal
2/64		950,700 gal	1,086,500 gal
3/64		978,500 gal	1,210,800 gal
4/64		1,053,200 gal	1,455,900 gal
5/64		965,400 gal	1,652,100 gal
6/64		1,214,000 gal	2,299,700 gal
7/64		1,427,100 gal	1,658,500 gal
8/64		1,450,900 gal	390,700 gal
9/64		1,150,100 gal	Out of Order


3-63 → 3-64
 24,962,500
 365 = 63400
 970

WELL WATER CONSUMPTION

<u>date</u>	<u>#N3450</u>	<u>#N5368</u>	<u>#N5390</u>
1/61		10,783,700 Gallons	335,600 Gallons
2/61		8,406,800 Gallons	134,800 Gallons
3/61		8,599,900 Gallons	134,300 Gallons
4/61		9,263,467 Gallons (Meter out of order. Above figure is an average of the past three months' total consumption for this well.)	389,000 Gallons
5/61		7,569,300 Gallons	240,600 Gallons
6/61		12,560,400 Gallons	813,800 Gallons
7/61		1,960,500 Gallons	1,387,800 Gallons
8/61		716,000 Gallons	2,301,800 Gallons
9/61		707,000 Gallons	1,150,900 Gallons (estimated reading - well is being repaired.)
10/61		973,900 Gallons	986,500 Gallons
11/61		1,792,100 Gallons	904,500 Gallons
12/61		793,700 Gallons	754,600 Gallons
1/62		735,200 Gallons	610,100 Gallons
2/62		274,400 Gallons	522,700 Gallons
3/62		265,500 Gallons	442,000 Gallons
4/62		315,300 Gallons	431,900 Gallons
5/62		406,100 Gallons	941,700 Gallons
6/62		1,599,000 Gallons	2,482,900 Gallons
8/62		587,000 Gallons	908,700 Gallons
9/62		410,500 Gallons	903,400 Gallons

WELL WATER CONSUMPTION

	<u>#N3450</u>	<u>#N5368</u>	<u>#N5390</u>
00	8,835,100 Gallons	3,523,300 Gallons	1,191,100 Gallons
1	well being repaired	2,104,900 "	790,900 "
60	" " "	7,198,500 "	1,230,000 "
6	" " "	9,503,700 "	653,100 "
60	8,300 Gallons	8,982,800 "	2,000 "
60	16,100 "	10,803,700 "	537,900 "
6	23,200 "	4,751,800 "	574,200 "
60	-	12,741,900 "	566,400 "
6	-	10,167,200 "	1,722,500 "
60	-	11,884,000 "	744,400 "
60	-	10,337,100 "	988,300 "
0	-	10,271,300 "	332,200 "



APPENDIX 14

HKR 001 1379

APPENDIX 14
Additional Water-Level Monitoring Data

HKR 001 1380

TABLE 1

**OCCIDENTAL CHEMICAL CORPORATION
HOOKER/RUCO SITE
HICKSVILLE, NEW YORK**

Summary of Monthly Water-Level Measurements

Well No.	TOC elevation (ft/msl)	Date	Depth to water (ft/btoc)	Water-level elevation (ft/msl)
A-1	137.51	01/24/92	62.88	74.63
		02/21/92	63.50	74.01
		03/27/92	63.93	73.58
		04/24/92	64.42	73.09
		05/29/92	65.96	71.55
		06/26/92	66.34	71.17
A-2	136.73	01/24/92	62.26	74.47
		02/21/92	62.83	73.90
		03/27/92	63.20	73.53
		04/24/92	63.80	72.93
		05/29/92	65.39	71.34
		06/26/92	65.79	70.94
B-1	132.65	01/24/92	58.30	74.35
		02/21/92	58.88	73.77
		03/27/92	59.33	73.32
		04/24/92	59.85	72.80
		05/29/92	61.42	71.23
		06/26/92	61.85	70.80
B-2	132.65	01/24/92	58.31	74.34
		02/21/92	58.88	73.77
		03/27/92	59.34	73.31
		04/24/92	59.88	72.77
		05/29/92	61.43	71.22
		06/26/92	61.86	70.79
C-1	135.61	01/24/92	58.77	76.84
		02/21/92	NM	-
		03/27/92	58.66	76.95
		04/24/92	59.34	76.27
		05/29/92	62.72	72.89
		06/26/92	62.71	72.90
C-2	133.55	01/24/92	61.46	72.09
		02/21/92	NM	-
		03/27/92	62.46	71.09
		04/24/92	63.01	70.54
		05/29/92	64.65	68.90
		06/26/92	65.05	68.50

HKR 001 1381

TABLE 1
(continued)

OCCIDENTAL CHEMICAL CORPORATION
HOOKER/RUCO SITE
HICKSVILLE, NEW YORK

Summary of Monthly Water-Level Measurements

Well No.	TOC elevation (ft/msl)	Date	Depth to water (ft/btoc)	Water-level elevation (ft/msl)
G-1	130.91	01/24/92	56.86	74.05
		02/21/92	57.43	73.48
		03/27/92	57.86	73.05
		04/24/92	58.39	72.52
		05/29/92	59.91	71.00
		06/26/92	60.37	70.54
G-2	130.56	01/24/92	56.53	74.03
		02/21/92	57.09	73.47
		03/27/92	57.54	73.02
		04/24/92	58.07	72.49
		05/29/92	59.60	70.96
		06/26/92	61.09	69.47
H-1	130.39	01/24/92	56.62	73.77
		02/21/92	57.11	73.28
		03/27/92	57.69	72.70
		04/24/92	58.15	72.24
		05/29/92	59.35	71.04
		06/26/92	60.06	70.33
H-2	130.17	01/24/92	56.48	73.69
		02/21/92	57.03	73.14
		03/27/92	57.46	72.71
		04/24/92	57.98	72.19
		05/29/92	59.54	70.63
		06/26/92	60.07	70.10
I-1	129.68	01/24/92	56.07	73.61
		02/21/92	56.60	73.08
		03/27/92	57.02	72.66
		04/24/92	57.53	72.15
		05/29/92	59.02	70.66
		06/26/92	59.60	70.08
I-2	130.02	01/24/92	56.44	73.58
		02/21/92	56.96	73.06
		03/27/92	57.39	72.63
		04/24/92	57.94	72.08
		05/29/92	59.46	70.56
		06/26/92	NM	-

HKR 001 1382

TABLE 1
(continued)

OCCIDENTAL CHEMICAL CORPORATION
HOOKER/RUCO SITE
HICKSVILLE, NEW YORK

Summary of Monthly Water-Level Measurements

Well No.	TOC elevation (ft/msl)	Date	Depth to water (ft/btoc)	Water-level elevation (ft/msl)
J-1	132.29	01/24/92	58.79	73.50
		02/21/92	59.40	72.89
		03/27/92	59.78	72.51
		04/24/92	60.34	71.95
		05/29/92	61.76	70.53
		06/26/92	62.36	69.93
J-2	132.28	01/24/92	58.91	73.37
		02/21/92	59.44	72.84
		03/27/92	59.83	72.45
		04/24/92	60.42	71.86
		05/29/92	61.93	70.35
		06/26/92	62.50	69.78
K-1	130.56	01/24/92	57.25	73.31
		02/21/92	57.86	72.70
		03/27/92	58.21	72.35
		04/24/92	58.79	71.77
		05/29/92	60.26	70.30
		06/26/92	60.84	69.72
K-2	130.55	01/24/92	57.29	73.26
		02/21/92	57.85	72.70
		03/27/92	58.21	72.34
		04/24/92	58.83	71.72
		05/29/92	60.29	70.26
		06/26/92	60.92	69.63
L-1	131.52	01/24/92	57.66	73.86
		02/21/92	58.28	73.24
		03/27/92	58.66	72.86
		04/24/92	59.24	72.28
		05/29/92	60.73	70.79
		06/26/92	61.25	70.27
L-2	131.68	01/24/92	57.99	73.69
		02/21/92	58.57	73.11
		03/27/92	58.94	72.74
		04/24/92	59.55	72.13
		05/29/92	61.12	70.56
		06/26/92	61.14	70.54

HKR 001 1383

TABLE 1
(continued)

OCCIDENTAL CHEMICAL CORPORATION
HOOKER/RUCO SITE
HICKSVILLE, NEW YORK

Summary of Monthly Water-Level Measurements

Well No.	TOC elevation (ft/msl)	Date	Depth to water (ft/btoc)	Water-level elevation (ft/msl)
M-1	135.61	01/24/92	61.36	74.25
		02/21/92	61.98	73.63
		03/27/92	62.37	73.24
		04/24/92	62.92	72.69
		05/29/92	64.45	71.16
		06/26/92	64.92	70.69
N-1	134.23	01/24/92	59.16	75.07
		02/21/92	NM	-
		03/27/92	60.26	73.97
		04/24/92	60.67	73.56
		05/29/92	61.99	72.24
		06/26/92	62.46	71.77
O-1	134.75	01/24/92	60.18	74.57
		02/21/92	60.88	73.87
		03/27/92	61.27	73.48
		04/24/92	61.76	72.99
		05/29/92	63.15	71.60
		06/26/92	63.65	71.10
P-1	132.32	01/24/92	58.52	73.80
		02/21/92	59.12	73.20
		03/27/92	59.50	72.82
		04/24/92	60.05	72.27
		05/29/92	61.58	70.74
		06/26/92	NM	-
Q-1	132.70	01/24/92	58.68	74.02
		02/21/92	59.29	73.41
		03/27/92	59.72	72.98
		04/24/92	60.22	72.48
		05/29/92	61.72	70.98
		06/26/92	62.22	70.48
R-1	136.07	01/24/92	60.91	75.16
		02/21/92	61.65	74.42
		03/27/92	62.02	74.05
		04/24/92	62.46	73.61
		05/29/92	63.83	72.24
		06/26/92	64.05	72.02

HKR 001 1384

TABLE 1
(continued)

OCCIDENTAL CHEMICAL CORPORATION
HOOKER/RUCO SITE
HICKSVILLE, NEW YORK

Summary of Monthly Water-Level Measurements

Well No.	TOC elevation (ft/msl)	Date	Depth to water (ft/btoc)	Water-level elevation (ft/msl)
S-1	133.21	01/24/92	57.27	75.94
		02/21/92	57.98	75.23
		03/27/92	58.22	74.99
		04/24/92	58.66	74.55
		05/29/92	59.91	73.30
		06/26/92	59.99	73.22
S-2	133.21	01/24/92	58.68	74.53
		02/21/92	59.17	74.04
		03/27/92	59.67	73.54
		04/24/92	60.07	73.14
		05/29/92	61.77	71.44
		06/26/92	62.13	71.08
T-1	131.21	01/24/92	57.01	74.20
		02/21/92	57.69	73.52
		03/27/92	58.06	73.15
		04/24/92	58.63	72.58
		05/29/92	60.16	71.05
		06/26/92	60.67	70.54
T-2	131.37	01/24/92	57.41	73.96
		02/21/92	58.03	73.34
		03/27/92	58.40	72.97
		04/24/92	59.03	72.34
		05/29/92	60.67	70.70
		06/26/92	60.60	70.77
N-10812	135.54	01/24/92	60.43	75.11
		02/21/92	60.99	74.55
		03/27/92	61.44	74.10
		04/24/92	61.98	73.56
		05/29/92	63.57	71.97
		06/26/92	63.87	71.67
N-10593	128.50	01/24/92	55.07	73.43
		02/21/92	55.67	72.83
		03/27/92	56.04	72.46
		04/24/92	56.59	71.91
		05/29/92	58.02	70.48
		06/26/92	58.63	69.87

HKR 001 1385

TABLE 1
(continued)

OCCIDENTAL CHEMICAL CORPORATION
HOOKER/RUCO SITE
HICKSVILLE, NEW YORK

Summary of Monthly Water-Level Measurements

Well No.	TOC elevation (ft/msl)	Date	Depth to water (ft/btoc)	Water-level elevation (ft/msl)
PM-1	132.87	01/24/92	58.66	74.21
		02/21/92	59.29	73.58
		03/27/92	59.75	73.12
		04/24/92	60.25	72.62
		05/29/92	61.63	71.24
		06/26/92	62.12	70.75
PM-2	127.99	01/24/92	54.92	73.07
		02/21/92	55.56	72.43
		03/27/92	55.96	72.03
		04/24/92	56.45	71.54
		05/29/92	NM	-
		06/26/92	NM	-
Airfield well (N10594)	126.66	01/24/92	53.98	72.68
		02/21/92	54.52	72.14
		03/27/92	54.85	71.81
		04/24/92	55.49	71.17
		05/29/92	56.85	69.81
		06/26/92	57.50	69.16
S.D. Bay Well (N10599)	107.60	01/24/92	40.81	66.79
		02/21/92	40.94	66.66
		03/27/92	41.68	65.92
		04/24/92	41.92	65.68
		05/29/92	41.80	65.80
		06/26/92	41.19	66.41
USGS Basin Well (out) (N10597)	109.85	01/24/92	40.17	69.68
		02/21/92	40.56	69.29
		03/27/92	40.94	68.91
		04/24/92	41.48	68.37
		05/29/92	42.04	67.81
		06/26/92	42.44	67.41

occhic.tbl/92-35

17

APPENDIX 15
Surveyor's Report

HKR 001 1388

Nassau County
Bench Marks
Department of Public Works
Highways & General Engineering
NASSAU COUNTY BENCH MARKS
Introduction

Mike Young
525-4033
1981

Bench marks listed in this book have been established by the topographic Section of the Department of Public Works.

PROCEDURE:

Prior to 1932, all spirit level work throughout the County was done by using an arbitrary datum, differing according to locality and the engineer doing the work.

Cognizant of the need for a uniform datum, the County Engineer, in 1932 caused to be established a County-wide system of Vertical Control; one result of this project was the publication of the first edition of the "County of Nassau Bench Marks" book in 1934.

DATUM:

The datum plane used on this project is based on mean sea level at Sandy Hook, New Jersey, as determined by the United States Coast and Geodetic Survey by observations and records of tidal gauges over a period of years. Mean sea level is the average height of the sea at the stages of the tide being considered.

As there were several of the United States Coast and Geodetic Survey bench marks located throughout the County, the "County Vertical Control" network was expanded from these.

BENCH MARK IDENTIFICATION:

The County Standard bench mark monument set prior to 1949 is a concrete truncated pyramid being four feet deep with an eight inch square and an eight inch square top. A bronze cylindrical plug three quarters of an inch in diameter and one and three quarters of an inch long is inserted to a depth to allow protrusion approximately one eighth of an inch above the top of the concrete. The elevation given is the top of this plug.

All monuments set since 1949 have a disc similar in size and shape to the United States Coast and Geodetic survey bronze disc. Its face stamped as follows: Department of Public Works, Nassau County, Bench Mark, Elev....FT....; \$250 fine for disturbing this mark. The elevation given is at the top center of the disc. Other primary bench marks have been established on solid structures such as catch basins, head walls, etc., a cut in the concrete defines the point of elevation.

ACCURACY OF ELEVATIONS:

All elevations in this book are to the nearest thousandths of a foot above the County datum.

All leveling was held well within the specifications of the first order leveling of the Board of Surveys and maps of the Federal Government. The allowable error of closure under the specifications mentioned above is 0.017 feet per circuit mile. The actual average error of closure in Nassau County was 0.0097 feet per circuit mile based on the original network of 435 linear miles.

The allowable error as established by Nassau County for all circuits was governed by the following formula: Four ten thousandths times the square root of the distance in feet. ($0.0004 \sqrt{\text{distance in feet}}$)

CHANGE IN BENCH MARKS:

Although a bench mark may appear to be quite permanent in character, the elevation may have been changed due to settling or other uncontrollable circumstances. Engineers are therefore cautioned to tie in with two or more bench marks whenever possible.

NASSAU COUNTY DEPT. OF PUBLIC WORKS - BENCHMARKS

14S03 G395 HICKSVILLE OYSTER BAY 08/76 26
 ELEV. 134.965 SQ. CUT ON WEST CURB OF BROADWAY DIRECTLY IN
 FRONT OF LILCO. POLE NO. 22. 358' NORTH OF CENT. LINE OF FARM LN.
 CK 9/69 RN 8/76 GR

14S04 G396 HICKSVILLE OYSTER BAY 08/76 26
 ELEV. 114.179 SQ. CUT ON CONC. FOOTING OF FENCE ON NORTHEAST
 CORNER OF SUMP NO. 159 25.5' WEST OF CENT. LINE OF BLOOMINGDALE RD.
 270.5' NORTH OF CENT. LINE OF MICHIGAN DRIVE 200' SOUTH OF CENT.
 LINE INTERSECTION WITH BROADWAY CK 5/67 MX 8/76 GR

14S05 G399 BETHPAGE OYSTER BAY 08/76 26
 ELEV. 116.124 SQ. CUT ON SOUTHWEST CORNER OF LIGHT STANDAR OF
 VEEDOL GAS STA. 30' EAST OF CENT. LINE OF HICKSVILLE RD. 139'
 NORTH OF CENT. LINE OF LOUIS ST. CK 11/57 WA 8/62 MX 1/64 MX
 5/67 MX 8/76 GR

14S06 G395A HICKSVILLE OYSTER BAY 02/78 26
 ELEV. 134.987 SQ. CUT ON THE WESTSIDE OF CONC. CURB OF LEE AVE.
 ON THE EXT'D CENT. LINE OF FARM LANE. CK 2/78 GR

14S07 G512 HICKSVILLE OYSTER BAY 08/76 26
 ELEV. 131.368 SQ. CUT ON WEST WALL CENT. OF 16.7'X10.7' CONC.
 METER PIT 30.5' EAST OF CENT. LINE OF NEW SOUTH RD. ON NORTH SIDE
 OF ENTRANCE OF RUBBER CORPORATION OF AMERICA 315' NORTH OF CENT.
 LINE OF DOUBLE TRACKS OF RAILROAD 9.5' SOUTH OF LILCO. POLE NO. 19.
 CK 5/67 MX 8/76 GR

14S08 G519 HICKSVILLE OYSTER BAY 08/76 26
 ELEV. 119.988 SQ. CUT IN CENT. OF SIDEWALK 40' EAST OF CENT.
 LINE OF TRAVELED RJ. OF NEW SOUTH RD. 30' SOUTH OF CENT. LINE C
 MULBERRY ST. CK 12/57 MX 8/62 MX 5/67 MX 8/76 GR

14S09 G653 HICKSVILLE OYSTER BAY 08/62 26
 ELEV. 111.474 SQ. CUT ON SOUTH WALL OF CATCHBASIN 18' WEST OF
 CENT. LINE OF BLOOMINGDALE RD. 53' SOUTH OF NYT POLE NO. 103
 557' SOUTH OF CENT. LINE OF MICHIGAN DRIVE 157'
 NORTH OF CENT. LINE OF SCHRIMPE COURT CK 8/62 MX

14S10 H284X HICKSVILLE OYSTER BAY 08/76 26
 ELEV. 124.807 SQ. CUT ON NORTH CURB OF GERALD ST. 96.5' EAST
 OF CENT. LINE OF BROADWAY CK 9/69 RN 8/76 GR

14S11 H521 HICKSVILLE OYSTER BAY 02/78 26
 ELEV. 133.176 SQ. CUT ON WEST CURB OF BROADWAY 47.5' SOUTH OF
 CENT. LINE OF LEWIS ST. DIRECTLY IN FRONT OF LILCO. POLE NO. 29.
 CK 9/69 RN 2/78 GR

14S12 H523 HICKSVILLE OYSTER BAY 02/78 26
 ELEV. 125.451 SQ. CUT ON EAST CURB OF GARDEN BLVD. ON EXT'D.
 CENT. LINE OF BALSAM LN. CK 12/69 RN 2/78 GR

*GROUND SHOTS

Fri Feb 16 09:04:02 1990

Point	Coordinates	Elevation	Desc / Type
290	N E 2137310 194316	132.96	M-1
320	N E 2136768 194488	130.50	B-1
321	N E 2136768 194488	130.49	B-2
322	N E 2136922 194178	130.47	Q-1
323	N E 2136821 194251	128.98	G-1
324	N E 2136809 194260	128.90	G-2
326	N E 2137170 193937	130.75	H-1
327	N E 2137164 193943	130.65	H-2
335	N E 2137640 194248	132.79	O-1
339	N E 2137655 194030	130.11	D-1
341	N E 2137655 194030	130.05	D-2
348	N E 2137634 193893	130.00	P-1
350	N E 2137685 193872	130.19	E-2
361	N E 2137634 193642	129.84	F-2
363	N E 2137547 193640	129.82	J-1
366	N E 2137541 193643	129.68	J-2
370	N 2137339	130.38	I-1

HKR 001 1391

	E	193796		
372	N	2137333	130.40	I-2
	E	193800		
409	N	2137683	128.6	K-1
	E	193569		
410	N	2137678	128.8	K-2
	E	193575		
412	N	2137709	129.9	L-1
	E	193970		
413	N	2137709	129.94	L-2
	E	193980		
421	N	2137936	131.68	T-1
	E	194232		
422	N	2137935	131.75	T-2
	E	194243		
424	N	2137635	133.54	S-1
	E	194693		
425	N	2137634	133.61	S-2
	E	194702		
427	N	2137538	134.04	R-1
	E	194551		
432	N	2137558	131.7	C-2
	E	194353		
434	N	2137539	131.5	N-1
	E	194346		
440	N	2137640	132.83	O-1
	E	194248		
381	N	2137495	134.16	A-1
	E	194562		
27	N	2136158	128.34	PM-2
	E	193170		
29	N	2136038	133.14	PM-1
	E	194124		

1"=50' DWG

Drawing: ' OXYPNTS' (OXY50.DAT)

Wed Jan 31 10:35:46 1990

Point		Coordinates	Elevation	Desc / Type
225	N	194544.61	136.00	AM-1 AIR MONITOR
	E	2136941.86		
242	N	193996.05	134.59	AM-5 AIR MONITOR
	E	2137096.99		
301	N	194442.40	135.72	AM-2 AIR MONITOR
	E	2137555.57		
329	N	194029.61	133.17	AM-3 AIR MONITOR
	E	2137653.39		
354	N	193692.85	132.31	AM-4 AIR MONITOR
	E	2137589.27		
226	N	194477.19	132.1	SG-2
	E	2136937.99		
227	N	194427.07	131.6	SG-3
	E	2136940.57		
228	N	194377.21	131.4	SG-4
	E	2136942.86		
229	N	194327.25	130.9	SG-5
	E	2136945.04		
230	N	194277.37	130.9	SG-6
	E	2136947.33		
231	N	194227.42	130.7	SG-7
	E	2136949.07		
232	N	194177.50	130.2	SG-8
	E	2136951.08		
236	N	194128.55	130.8	SG-9
	E	2137003.02		
239	N	194129.68	131.9	SG-16
	E	2137053.53		
246	N	194131.17	131.7	SG-19
	E	2137103.06		
252	N	194181.05	131.4	SG-18
	E	2137101.23		
251	N	194182.50	132.5	SG-20
	E	2137151.34		

HKR 001 1393

271	N E	194576.95 2136933.01	133.2	SG-1
253	N E	194179.45 2137051.20	131.1	SG-15
254	N E	194178.50 2137001.21	130.8	SG-10
255	N E	194231.41 2137002.31	130.9	SG-11
256	N E	194229.78 2137049.14	131.0	SG-14
257	N E	194278.44 2136997.08	131.4	SG-12
263	N E	194279.62 2137047.09	132.0	SG-13
267	N E	194231.11 2137099.21	132.0	SG-17
401	N E	193704.26 2137583.72	128.9	SG-61
426	N E	194566.52 2137242.56	133.8	SG-53
428	N E	194593.95 2137604.89	133.8	SG-58
429	N E	194436.03 2137393.28	132.7	SG-77
430	N E	194373.07 2137561.48	131.6	SG-80
431	N E	194465.73 2137544.92	133.6	SG-79
435	N E	194510.87 2137286.10	133.6	SG-23
436	N E	194360.89 2137274.83	132.4	SG-36
438	N E	194186.38 2137658.51	131.4	SG-50
439	N E	194238.33 2137647.71	132.1	SG-49
441	N E	194335.11 2136888.82	130.0	SG-37

442	N E	194185.82 2136895.73	130.3	SG-40
405	N E	193789.63 2137651.24	124.6	SG-67
338	N E	194029.70 2137655.00	132.35	D-1 MON WELL
201	N E	194488.16 2136767.55	132.65	B-1 MON WELL
202	N E	194488.37 2136767.74	132.65	B-2 MON WELL
214	N E	194177.62 2136921.66	132.70	Q-1 MON WELL
222	N E	194250.82 2136821.23	130.91	G-1 MON WELL
224	N E	194259.77 2136809.14	130.56	G-2 MON WELL
244	N E	193937.20 2137169.72	130.39	H-1 MON WELL
245	N E	193943.31 2137164.17	130.17	H-2 MON WELL
276	N E	194315.98 2137309.86	135.61	M-1 MON WELL
383	N E	193871.56 2137684.88	132.98	E-1 MON WELL
349	N E	193871.85 2137684.90	132.71	E-2 MON WELL
360	N E	193641.67 2137634.01	131.54	F-2 MON WELL
362	N E	193639.71 2137546.68	132.29	J-1 MON WELL
365	N E	193642.66 2137541.48	132.28	J-2 MON WELL
371	N E	193800.16 2137333.14	130.02	I-2 MON WELL
382	N E	194603.70 2137301.17	136.73	A-2 MON WELL
369	N E	193795.99 2137338.82	129.68	I-1 MON. WELL
340	N	194029.61	132.21	D-2 MON WELL

	E	2137655.33		
380	N	194603.30	137.51	A-1 MON.WELL
	E	2137301.10		
358	N	193641.72	131.81	F-1 MON.WELL
	E	2137633.60		
347	N	193893.35	132.32	P-1 MON WELL
	E	2137634.40		
452	N	194352.78	133.55	C-2 MON WELL
	E	2137558.16		
453	N	194352.71	135.61	C-1 MON WELL
	E	2137558.46		
454	N	194345.53	134.23	N-1 MON WELL
	E	2137539.08		
419	N	193876.07	132.00	PLANT WELL #3
	E	2137550.26		
455	N	194247.60	134.75	O-1 MON WELL
	E	2137640.38		
451	N	194551.34	136.07	R-1 MON WELL
	E	2137537.56		
278	N	194402.73	133.5	TB-25
	E	2137305.09		
283	N	194571.99	134.1	TB-22
	E	2137605.19		
288	N	194442.53	134.1	TB-26
	E	2137396.96		
291	N	194496.62	133.5	TB-27
	E	2137420.79		
298	N	194461.11	133.02	TB-20
	E	2137612.62		
299	N	194519.27	133.5	TB-21
	E	2137608.54		
302	N	194415.94	132.49	TB-19
	E	2137543.80		
306	N	194368.08	131.66	TB-18
	E	2137543.63		
307	N	194349.83	126.6	TB-28
	E	2137581.46		
308	N	194308.96	125.4	TB-29
	E	2137611.59		

310	N E	194115.37 2137491.39	129.69	TB-39
311	N E	194150.86 2137494.33	130.49	TB-40
312	N E	194109.70 2137557.08	129.97	TB-12
313	N E	194111.14 2137584.35	130.2	TB-13
314	N E	194080.59 2137663.94	129.85	TB-8
315	N E	194107.12 2137662.08	130.5	TB-9
316	N E	193998.21 2137458.81	130.68	TB-37
317	N E	193987.04 2137473.17	130.8	TB-38
330	N E	194148.43 2137621.38	130.92	TB-17
331	N E	194163.76 2137601.62	131.08	TB-15
332	N E	194131.06 2137601.86	130.66	TB-14
333	N E	194183.95 2137611.15	131.0	TB-16
336	N E	194165.28 2137654.22	130.8	TB-11
337	N E	194142.87 2137662.18	130.7	TB-10
342	N E	193999.04 2137575.72	129.7	TB-35
343	N E	194000.53 2137559.07	129.8	TB-34
344	N E	193944.34 2137646.36	117.9	TB-31
345	N E	193916.42 2137651.59	117.0	TB-30
346	N E	193899.01 2137627.13	129.9	TB-P1

HKR
001
1397

351	N E	193804.28 2137567.20	130.2	TB-24
352	N E	193733.70 2137587.66	126.0	TB-23
353	N E	193661.34 2137574.65	129.8	TB-2
355	N E	193740.16 2137640.58	124.5	TB-5A
356	N E	193745.65 2137643.22	125.1	TB-5
357	N E	193707.79 2137696.13	116.7	TB-32
367	N E	193677.67 2137502.78	129.7	TB-1
373	N E	194019.10 2137488.69	130.14	TB-36
374	N E	193677.91 2137673.34	116.0	TB-33
375	N E	193792.19 2137530.33	130.6	TB-7
376	N E	193806.32 2137508.94	131.0	TB-6
377	N E	193767.78 2137456.77	129.8	TB-3
378	N E	193749.65 2137483.60	129.5	TB-4
221	N E	194242.34 2136821.90	128.9	TB-GP
243	N E	193930.88 2137175.86	130.77	TB-HP
364	N E	193636.20 2137553.93	129.38	TB-JP
368	N E	193791.27 2137344.82	130.25	TB-IP
402	N E	193710.48 2137568.84	128.9	TB-43
403	N E	193789.09 2137579.29	129.8	TB-41
404	N	193801.37	129.6	TB-44

HKR 001 1398

	E	2137666.95		
406	N	193703.95	129.3	TB-46
	E	2137637.92		
407	N	193664.93	129.7	TB-45
	E	2137580.02		
414	N	193959.50	129.9	TB-49
	E	2137608.42		
415	N	193980.95	129.4	TB-50A
	E	2137678.13		
416	N	193879.94	129.2	TB-48
	E	2137662.76		
417	N	193805.57	130.7	TB-42
	E	2137559.38		
418	N	193841.05	131.2	TB-47
	E	2137561.95		
272	N	194587.09	134.0	BB
	E	2137306.89		
273	N	194567.36	133.8	CC
	E	2137308.53		
274	N	194551.76	133.7	DD
	E	2137310.96		
275	N	194560.10	134.3	FF
	E	2137407.67		
277	N	194530.89	133.7	GG
	E	2137304.98		
279	N	194574.44	133.5	EE
	E	2137532.98		
280	N	194545.66	133.8	FF-1
	E	2137587.84		
281	N	194546.70	133.6	EE-1
	E	2137608.32		
285	N	194384.45	131.8	OO
	E	2137376.05		
286	N	194403.34	131.9	NN
	E	2137388.08		
287	N	194421.64	132.6	MM
	E	2137406.82		
289	N	194440.46	132.6	LL
	E	2137422.78		

HKR 001 1399

290	N E	194459.15 2137437.33	133.0	KK
292	N E	194518.21 2137437.53	137.1	HH
293	N E	194530.40 2137530.59	133.6	GG-1
294	N E	194513.59 2137522.13	133.8	HH-1
295	N E	194489.39 2137537.50	133.8	II-1
296	N E	194453.58 2137510.58	133.2	KK-1
297	N E	194434.42 2137486.87	132.9	JJ-1
300	N E	194618.04 2137619.65	134.2	BB-1
303	N E	194409.28 2137548.68	132.3	MM-1
304	N E	194389.30 2137546.63	132.0	NN-1
305	N E	194369.47 2137544.66	131.5	OO-1
318	N E	194637.58 2137617.09	133.9	AA-1
309	N E	194597.04 2137621.10	133.8	CC-1
203	N E	194336.49 2136790.88	129.8	A
204	N E	194331.12 2136811.02	129.4	B
205	N E	194333.97 2136830.44	129.3	C
206	N E	194334.18 2136850.17	129.4	D
207	N E	194335.38 2136870.16	129.6	E
209	N E	194337.45 2136900.13	130.1	FG

HKR 001 1400

210	N E	194339.76 2136910.62	130.4	G
211	N E	194340.89 2136930.13	130.9	H
212	N E	194158.34 2136936.55	130.4	H-1
213	N E	194170.79 2136919.52	130.3	G-1
215	N E	194178.37 2136909.29	130.2	FG-1
216	N E	194185.72 2136895.56	130.2	F-1
217	N E	194199.38 2136879.37	129.8	E-1
218	N E	194210.89 2136861.95	129.7	D-1
219	N E	194223.29 2136843.99	129.5	C-1
220	N E	194234.88 2136824.86	129.2	B-1
223	N E	194249.77 2136808.30	128.9	A-1
233	N E	194141.50 2136957.81	130.5	I-1
234	N E	194140.50 2136977.80	130.7	J-1
235	N E	194137.38 2136996.90	131.2	K-1
237	N E	194137.94 2137017.88	131.3	L-1
238	N E	194137.32 2137037.98	131.7	M-1
240	N E	194136.63 2137057.77	131.7	N-1
241	N E	194135.72 2137078.08	132.0	O-1
247	N E	194135.46 2137097.92	132.2	P-1
248	N	194139.70	132.0	Q-1

	E	2137117.82		
249	N	194142.00	132.3	R-1
	E	2137137.79		
250	N	194149.36	132.3	S-1
	E	2137156.93		
258	N	194341.57	131.3	I
	E	2136950.84		
259	N	194332.31	131.6	J
	E	2136971.82		
260	N	194321.36	131.5	K
	E	2136990.83		
261	N	194311.12	131.8	L
	E	2137011.34		
262	N	194293.28	132.0	M
	E	2137031.82		
264	N	194280.41	132.2	N
	E	2137052.27		
265	N	194263.65	132.1	O
	E	2137072.63		
266	N	194245.32	132.2	P
	E	2137093.02		
268	N	194228.23	132.5	Q
	E	2137114.02		
269	N	194211.95	132.1	R
	E	2137134.30		
270	N	194195.64	132.6	S
	E	2137155.05		
379	N	194606.48	134.0	AA
	E	2137298.66		

1" = 200' DWG

Drawing: ' OXY200'

Wed Jan 31 10:34:19 1990

Point		Coordinates	Elevation	Desc / Type
408	N	193562.41	128.6	KP
	E	2137687.73		
411	N	193957.63	129.8	LP
	E	2137711.67		
423	N	194685.62	133.6	SP
	E	2137634.04		
420	N	194225.20	131.6	TP
	E	2137935.92		
338	N	194029.70	132.35	D-1 MON WELL ✓
	E	2137655.00		
201	N	194488.16	132.65	B-1 MON WELL ✓
	E	2136767.55		
202	N	194488.37	132.65	B-2 MON WELL ✓
	E	2136767.36		
214	N	194177.62	132.70	Q-1 MON WELL ✓
	E	2136921.66		
222	N	194250.82	130.91	G-1 MON WELL ✓
	E	2136821.23		
224	N	194259.77	130.56	G-2 MON WELL ✓
	E	2136809.14		
244	N	193937.20	130.39	H-1 MON WELL ✓
	E	2137169.72		
245	N	193943.31	130.17	H-2 MON WELL ✓
	E	2137164.17		
276	N	194315.98	135.61	M-1 MON WELL ✓
	E	2137309.86		
334	N	194247.91	134.75	O-1 MON WELL ✓
	E	2137640.39		
383	N	193871.56	132.98	E-1 MON WELL ✓
	E	2137684.88		
349	N	193871.85	132.71	E-2 MON WELL ✓
	E	2137684.90		

HKR 001 1403

360	N E	193641.67 2137634.01	131.54	F-2 MON WELL ✓
362	N E	193639.71 2137546.68	132.29	J-1 MON WELL ✓
365	N E	193642.66 2137541.48	132.28	J-2 MON WELL ✓
371	N E	193800.16 2137333.14	130.02	I-2 MON WELL ✓
382	N E	194603.70 2137301.17	136.73	A-2 MON WELL ✓
369	N E	193795.99 2137338.82	129.68	I-1 MON.WELL ✓
340	N E	194029.61 2137654.67	132.21	D-2 MON WELL ✓
380	N E	194603.30 2137301.09	137.51	A-1 MON.WELL ✓
358	N E	193641.72 2137633.60	131.81	F-1 MON.WELL ✓
347	N E	193893.35 2137634.40	132.32	P-1 MON WELL ✓
443	N E	193569.07 2137682.51	130.56	K-1 MON WELL ✓
444	N E	193575.20 2137678.20	130.55	K-2 MON WELL ✓
445	N E	193970.12 2137709.17	131.52	L-1 MON WELL ✓
446	N E	193979.55 2137709.20	131.68	L-2 MON WELL ✓
447	N E	194232.31 2137935.62	131.21	T-1 MON WELL ✓
448	N E	194243.00 2137934.57	131.37	T-2 MON WELL ✓
449	N E	194693.41 2137634.91	133.21	S-1 MON WELL ✓
450	N E	194702.04 2137633.80	133.21'	S-2 MON WELL ✓

452	N	194352.78	133.55	C-2 MON WELL ✓
	E	2137558.16	135.55	
453	N	194352.71	135.61	C-1 MON WELL ✓
	E	2137558.46		
454	N	194345.53	134.23	N-1 MON WELL ✓
	E	2137539.08		
419	N	193876.07	132.00	PLANT WELL #1 ✓
	E	2137550.26	- 7.80'	
451	N	194551.34	136.07	R-1 MON WELL ✓
	E	2137537.56		
28	N	194046.41	132.87	PM-1 MON WELL ✓
	E	2136048.93		
29	N	194123.66	127.99	PM-2 MON WELL
	E	2136038.13		

Keweenaw Ln

N10812 135.54

Airfield

N10594 126.66

RRX

N10593 128.50

Junco

N10598 106.48

Inside usas

N10630 -? 110.66

outside


N10597 - 109.85

107-508R

N10599 - 107.60

Best Cas

130.50



LEGGETTE, BRASHEARS & GRAHAM, INC.

72 Danbury Road
Wilton, CT 06897
(203) 762-1207
FAX (203) 762-8062

HKR 001 1406